

SURVEY & REMONUMENTATION

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For recording in
SECTION
Allegan
 (County)

Located In: Corner Code #

- 1. Public Land Survey T 2N R 14W ✓ B-1
 T R N 1/4 Cor.
 T R Sec. 6
 T R Valley Twp.
- 2. Property Controlling S T R _____
 in Section S T R _____
- 3. Miscellaneous S T R _____
 Property in Sec. S T R _____

Register of Deeds
 ALLEGAN COUNTY, MICH.
Joyce A. L. ...

98 JAN 21 PM 1:37

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk L. Van Order, in a field survey on Oct. 27, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

B-1
 (1) Not set by G.L.O.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-11-97
 COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

B-1
 Kirk L. Van Order Remon. survey dated Oct. 27, 1997
 Set B-1 at prorated distance between C-1 and A-1 of T.2N., R.14W. and on line between C-13 of T.3N., R.14W. and A-1, T.2N., R.14W. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.
 2709.355' West to A-1
 2615.63' East to C-1

Peer group approved Nov. 11, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1
 Set A.C. Remon. monument (3/4" x 36" steel rod w/red plastic cap #23520)
 Nail & Remon. tag in SW side 15" Oak AZ 320° 95.14'
 Nail & Remon. tag in W. side 10" W. Pine AZ 00° 13.04'
 Nail & Remon. tag in S. side 28" W. Pine AZ 75° 14.77'
 Nail & Remon. tag in E. side 28" W. Oak AZ 190° 65.09'
 North edge of asphalt Hwy. M-89 AZ 180° 9.9'

Signed by *Kirk L. Van Order*
 Surveyor's Michigan License No. 23520

Date 12-31-97