

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

ALLEGAN (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>2N</u> R <u>14W</u>	<u>B-13</u>
	T ___ R ___	<u>Valley Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN

1994 DEC 16 AM 9:55

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	15	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald R. Pitts Jr., in a field survey on August 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.-Set $\frac{1}{4}$ Section Post
 W. Oak 18" N.60°E. 35 Links
 Pine 8" N.71°W. 38 Links


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No Corner Found
 Set Standard Allegan Co. Remon. 3/4"x24" Iron with Red Cap 23520 on line from B-1, T.1N., R.14W., to A-13, T.2N., R.14W., 76.07' West of B-1, Prorated Distance from A-13.
 Traversed 2639' East & 2390' West
 Approved by the Allegan Co. Remon. Peer Group, April 12, 1994, and is accepted as a careful and faithful reestablishment of the position of the original corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-12-94
 COUNTY REP. Paul J. Van Pelt

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Allegan Co. Remon. 3/4"x24" Iron with red cap 23520
 B-1, T.1N., R.14W., Standard Allegan Co. Remon. 3/4"x24" Iron with red cap 23520
 Nail & Allegan Co. Remon tag N. Side 12" Oak S.70°W. 59.55'
 " " " " " S.W. Side 22" Oak N.50°W. 35.18'
 " " " " " S. Side 14" Oak N.45°E. 41.20'



Signed by Donald R. Pitts Jr. Date 30 August 1994

Surveyor's Michigan License No. 25867

LIBER 0005 PAGE 036