

REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

ALLEGAN
(County)

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

	Located in:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>14W</u>	<u>C-13</u>
	T _____ R _____	<u>Valley Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

J. Edgar A. [Signature]
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.

1994 DEC 16 AM 9:55

FILED

Register of Deeds Stamp & File Number

I, Donald R. Pitts Jr., in a field survey on August 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessions and/or subsequent restoration:
 G.L.O.-Set Corner Section 31 & 32
 30" Pine N.43°W. 8 Links
 10" Lynn N.63°E. 34 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No Corner Found.
 Set standard Allegan Co. Remon. 3/4"X24" Iron with red cap 23520 on line between C-1, T.1N., R.14W., and B-1, T.1N., R.14W., at G.L.O. Jog 75.90' (115 Links) West of C-1, T.1N., R.14W.
 Traversed 2605' EAST & 2639' WEST
 Approved by Allegan Co. Remon. Peer Group April 12, 1994, and is accepted as a careful and faithful reestablishment of the position of the original corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-12-94
 COUNTY REP. [Signature]

C. Description of monument for corner and accessions established to perpetuate locating the position of the corner:
 Standard Allegan Co. Remon. 3/4"X24" Iron with Red Cap 23520.
 C-1, T.1N., R.14W., Standard Allegan Co. Remon. 3/4"X24" Iron with Red Cap 23520 East 75.90'.
 Nail & Allegan Co. Remon. Tag in top of wood Guard Post N.70°E. 63.30'
 " " " " " " " " " " " S.30°E. 20.23'
 " " " " " " " " " " " S.70°W. 43.94'



Signed by Donald R. Pitts Jr.
 Surveyor's Michigan License No. 25867
 LIB# 0005 PAGE 037

Date 30 August 1994