

**SURVEY & REMONUMENTATION**

APR 07 1998

**SECTION**

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>14W</u>	✓ D-1
	T _____ R _____	N 1/4 Cor.
	T _____ R _____	Sec. 5
	T _____ R _____	Valley Twp.
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

98 JAN 21 PM 1:37  
*Joyce A. Bennett*  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICH.

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk L. Van Order, in a field survey on Sept. 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-1  
 (1) Not set by original government surveyors

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 8-12-97  
 COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1  
 Remon. survey Sept. 4, 1997, Kirk L. Van Order  
 Fd. no evidence of corner and set D-1 midway between E-1 and C-1 on line between E-13 of T.4N., R.14W. and C-1 of T.2N., R.14W.  
 This position not established by original government surveyors.  
 This monument is accepted as the best available evidence of the position of the corner.  
 Peer group approved Aug. 12, 1997.  
 D-1 to D-13 T.3N., R.14W. S88°32'25"W 270.90'  
 D-1 to E-13 T.3N., R.14W. N88°32'25"E 2431.05'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1  
 Set A.C. Remon. monument (3/4" x 36" steel rod w/red plastic cap #23520)  
 Nail & Remon. tag in SW side 14" Maple N40°W 12.65'  
 Nail & Remon. tag in SE side 4" Ash N10°E 8.23'  
 Nail & Remon. tag in N. side 14" Maple S80°E 35.35'  
 Nail & Remon. tag in S. side 16" Ash N70°W 27.48'  
 (Note: Blazed all trees)

Signed by *Kirk L. Van Order* Date 12-31-97  
 Surveyor's Michigan License No. 23520

LIBER 0006 PAGE 233