

SURVEY & REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION For corners in

<u>Allegan</u> (County)	Located in:	Corner Code <u>##</u>
1. Public Land Survey	T <u>2N</u> R <u>14W</u>	<u>E-1</u>
	T ___ R ___	<u>NW Cor.</u>
	T ___ R ___	<u>Sec. 4</u>
	T ___ R ___	<u>NE Cor.</u>
2. Property Controlling in Section	S ___ T ___ R ___	<u>Sec. 5</u>
	S ___ T ___ R ___	<u>Valley Twp.</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

1994 DEC 30 PM 12:16
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 Joyce A. Ebert

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Kirk Van Order, in a field survey on March 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1
 •86.52 N of E-3 to E-1 (N boundary)
 GLO set corner post 299 links East of E-13 in Heath Twp.
 12" Pine S27°W 21 links •No LCRC or other surveys found
 5" Dogwood S56°E 19 links
 •Ratekin notes references old unspecified notes
 N Corner 4 & 5
 M.S.H.D. B.M. cap in root 20" Maple N73°W 37.04'
 20" Maple N12°W 46.04'
 10" Oak N36°E 27.05'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1
 Fd. stone S10°17'20"W. 0.97' from E-1 position as set.
 Set E-1 position on Township line S90°00'00"E 197.34' from E-13 and
 N90°00'00"W 2442.13 feet from F-13 Heath Twp. corners.

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Peer Group approved 3-9-94.

2639.47' on road traverse

APPROVED REMONUMENTATION CORNER

P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-9-94
 COUNTY REP. Kirk Van Order

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1
 Set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
 High point of stone S10°17'20"W 0.97'
 Nail & Remon. tag in E side 21" W. Oak N20°E 13.73'
 Nail & Remon. tag in NE side 22" Twin Red Oak N30°W 55.98'
 Nail & Remon. tag in N side 44" Twin Maple N70°W 55.90'
 Nail & Remon. tag in SW side 30" Maple N5°W 45.15'
 Nail & Remon. tag in N side 8" W. Pine N85°E 37.18'
 E-13 Heath Twp. corner S90°00'00"W 197.34'

Signed by [Signature]
 Surveyor's Michigan License No. 23520

Date 12-30-94

LIBER 0005 PAGE 102