

**SURVEY
REMONUMENTATION**

APR 20 1999

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

SECTION

FILED

LIBER 007 PAGE 08

FOR CORNERS IN: ALLEGAN COUNTY

LOCATED IN: T.....^{2N} R.....^{14W} CORNER CODE # E-6

1. Public Land Survey

1/4 SEC. COR COMMON TO SEC. 16 & 17 VALLEY TOWNSHIP

2. Property Controlling in section

3. Miscellaneous Property in Sec.

4. Lot No.....Recorded Plat.....

5. Private Claims.....

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-
-40.00 SET QR. SEC. POST FROM WHICH
A PINE 15 IN DIA BEARS S83E 15 LINKS
A BEECH 10 IN DIA BEARS N85W 22 LKS

J. RANDOLPH HEPWORTH, RECORDED L.C.R.C., LIBER 5, PAGE 335, MAY 20, 1996

E-6 TO E-5		NORTH 2608.62'
E-6 TO E-7		SOUTH 2621.04'
60d SPK, S. FACE	36" OAK (OBT)	295° AZ 125.17'
AS RECORDED	18" W OAK	N71°-15' W 123.6'
60d SPK, N.W. FACE	CLP 10"-12" W OAK	234° AZ 21.30'
60d SPK, S.W. FACE	16" W OAK	145° AZ 31.78'
60d SPK, N. FACE	4" W PINE	91° AZ 43.00'
60d SPK, N.E. FACE	12" W OAK	341° AZ 18.40'
CENTER OF N-S TRAIL		EAST 9'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED Nov. 24, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CAPPED IRON #26457 (HEPWORTH) PER ACCESSORIES NOTED ABOVE IN LCRC.

- FD 60d SPK IN NW SIDE 30" OAK CLUMP S54°W 21.30'
- FD 60d SPK IN E SIDE 14" OAK N20°W 18.41'
- FD 60d SPK IN SW SIDE 20" OAK S35°E 31.80'
- SET 20d SPK IN NE SIDE 14" OAK N40°W 26.82'
- C/L N & S TRAIL EAST 10' +/-
- C/L TRAIL TO EAST NORTH 30' +/-

REMOVED CAPPED IRON AND SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP AT FOUND POSITION.

ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON NOV. 24, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.

- FD NAIL IN NW SIDE 30" W. OAK CLUMP S54°W 21.30'
- FD NAIL IN NE SIDE 14" W. OAK N20°W 18.41'
- FD NAIL IN SW SIDE 20" W. OAK S35°E 31.80'
- NAIL & TAG IN NE SIDE 14" W. OAK N40°W 26.82'
- C/L N & S TRAIL E 10' +/-
- C/L TRAIL TO E NORTH 30' +/-
- FACE 18" W. OAK N71°W 123.6'

Raymond Moored Date 12/1/98

Surveyors License No. 26463

