

**SURVEY  
REMONUMENTATION**

APR 9 1999

**SECTION**

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

FILED

1/28/1999 2:44:39 PM

JOYCE A. MATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

REGISTER OF DEEDS STAMP & FILE NUMBER

LIBERO 007 PAGE 10

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T..... <sup>2N</sup> R..... <sup>14W</sup>	E-8
1/4 SEC. COR COMMON TO SEC. 20 & 21 VALLEY TOWNSHIP	T..... R..... T..... R..... T..... R.....	..... ..... .....
2. Property Controlling in section	S..... T..... R..... S..... T..... R.....	..... .....
3. Miscellaneous Property in Sec.	S..... T..... R.....	.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	1	2	3	4	5	6	7	8	9	10	11	12
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	16	17	18	19	20	21	22	23	24	25	26	27	28
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- GLO- 40.00, SET POST COR SEC. 20 & 21 FROM WHICH  
A PINE 8IN DIA BEARS N6W 11LKS  
A PINE 29IN DIA BEARS S41E 27LKS
- COUNTY SURVEYOR FIELD NOTES: MAY 23, 1875  
FROM NE COR TO E 1/4 POST 39.37 CHS. VAR 4.26
- DONALD RATEKIN & ASSOC., SECTION CARD INFORMATION  
1" IRON  
-16" OAK SE 60.7'  
-ST SIGN SW 40.5'  
-14" OAK WNW 44.4'  
-14" OAK NNE 9.5'  
-TWIN OAKS NNE 46.4'  
-12" OAK NE 20.8'  
-C/L ROAD INTERSECTION 12' W & 5' S

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED NOV 24, 1998  
COUNTY REP. Raymond Moored

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- FD. 1-1/4" PIPE OVER 1" IRON ROD AT CORNER LOCATION.
- FD. C/L INTERSECTION 10' WEST AND 5' SOUTH
- FD. 16" OAK SE 60.7'
- FD. 14" OAK WNW 44.4'

REMOVED PIPE AND IRON BAR AND SET STANDARD ALLEGAN COUNTY REMON. IRON WITH CAP AT THIS POSITION.  
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON NOV. 24, 1998

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
- NAIL IN WEST SIDE 18" OAK S40°E 61.65'
  - NAIL IN SOUTH SIDE 10" OAK N70°E 51.80'
  - NE CORNER TCB S50°W 58.01'
  - NAIL IN SOUTH SIDE 13" OAK N80°W 43.62'
  - TO FACE OF STOP SIGN N50°E 24.53'
  - 10' EAST OF NORTH/SOUTH ROAD
  - 5' NORTH OF EAST/WEST ROAD

*Raymond Moored*

Date 12/1/98

Surveyors License No. 26463

