

SURVEY & REMONUMENTATION

APR 25 1995

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

<u>ALLEGAN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>14W</u>	<u>E-13</u>
	T _____ R _____	<u>Valley</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 1994 DEC 16 AM 9:55
 FILED

Register of Deeds Stamp & File Number

I, Donald R. Pitts, in a field survey on September 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O: Set post corner Sec. 32 & 33	Circa 1900: Allegan Co. Surveyor
30" Pine N.78°W. 22 Links	Iron
14" Pine N.68°E. 31 Links	S.W. Cor. House N.E. 105.5'
7-26-88 Allegan Co. Surveyor Kirk L. Van Order	10" W. Oak N.W. 58.9'
Found 1 1/4" Pipe	24" Elm N.E. 44.5'
N.W. Cor. Hse. Foundation N.E. 119.95'	26" TW B. Oak S.E. 85.0'
S.E. Cor. Hse. Foundation N.E. 131.95'	8" Spruce E.N.E. 65.9'
9" Red Pine S.W. 68.68'	
Power Pole N.W. 60.70'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1 1/4" Pipe
 N.W. Cor. House Foundation N.E. 119.95'
 S.E. Cor. House Foundation N.E. 131.95'
 Nail in 10" Red Pine S.W. 68.68'
 P.K. in Power Pole N.W. 60.70'
 Pulled Pipe and set Standard Allegan Co. Remon 3/4" X 24" Iron W/Red cap #23520.
 Approved by the Allegan Co. Remon Peer Group on April 12, 1994, and is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-12-94
 COUNTY REP. Richard J. [Signature]

Traversed 2640' East & 2604' West

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Allegan Co. Remon. 3/4" X 24" Iron W/Red Cap #23520
 E-1, T.1N., R.14W. Standard Allegan Co. Remon 3/4" X 24" Iron W/Red Cap #23520 East 3.40'
 Nail & Allegan Co. Remon Tag in S.W. Side Power Pole N.35°W. 60.69'
 " " " " " " S. Side 14" Spruce N.75°E. 65.86'
 " " " " " " S.E. Side 10" Red Pine S.55°W. 68.61'



Signed by Donald R. Pitts, Jr. Date 12 SEPT 1994

Surveyor's Michigan License No. 25867

LIBER 0005 PAGE 039