

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>14W</u>	G-1
	T ___ R ___	NW Cor.
	T ___ R ___	Sec. 3
	T ___ R ___	NE Cor.
2. Property Controlling in Section	S ___ T ___ R ___	Sec. 4
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	Valley Twp.
	S ___ T ___ R ___	

1994 DEC 30 PM 12:16
James A. [Signature]
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

1. Kirk Van Order, in a field survey on March 7, 19 94
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1
 •North 85.77 chains to N boundary, 198 links East of G-13 post, T.3N, R.14W.
 12" W. Oak S44°W 33 links
 8" Beech S44°E 36 links

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-9-94
 COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1
 Fd. 3/4" rerod with 2" galv. pipe on S side N01°57'33"W 2.24' from G-1 as set. Removed rerod and pipe. Was established using improper procedures and is not utilized in this survey.

Set G-1 position on Township line S89°56'19"E 130.68' from G-13 and N89°56'19"W 2514.83' from H-13 corners of Heath Twp., T.3N., R.14W.

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Peer Group approved 3-9-94.
 Traversed 2645.51 feet. (on road)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1
 Set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
 Nail & Remon. tag in SE side 20" B. Oak N25°E 11.06'
 Nail & Remon. tag in SW side 8" W. Oak S60°E 11.94'
 Nail & Remon. tag in S side 12" Twin B. Oak N50°W 22.04'
 Nail & Remon. tag in SE side 7" W. Pine S50°W 24.43'

Signed by *[Signature]* Date 12-30-94
 Surveyor's Michigan License No. 23520

KEEP 0005 PAGE 103