

**SURVEY & REMONUMENTATION**

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**  
For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T 2N R 14W	✓ H-1
	T R	N 1/4 cor.
	T R	Sec. 3
	T R	Valley Twp.
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

98 JAN 21 PM 1:37  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
*James A. Carter*

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk L. Van Order, in a field survey on Sept. 9, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	N
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-1  
(1) Not set by original government surveyors

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 9-9-97  
COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1  
Kirk L. Van Order Remon. survey dated Sept. 9, 1997  
Fd. D.N.R. concrete monument 0.14' South and 0.075' East of a point midway between I-1 and G-1 of T.2N., R.14W. and from a line between H-13 and I-13 of T.3N., R.14W. On Sept. 23, 1997 adjusted said monument North to townline and West to midway between G-1 and I-1 of T.2N., R.14W. And is accepted as a careful and faithful reestablishment of the position of the original corner.

Peer group approved Sept. 9, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1  
Reset D.N.R. concrete monument with a 4" x 36" concrete monument with an aluminum plate on top  
H-3, T.3N., R.14W. AZ 270° 102.605'  
I-13, T.3N., R.14W. AZ 90° 2554.065'  
Nail & Remon. tag in S side 12" White Oak AZ 90° 77.84'  
Nail & Remon. tag in SE side 13" White Oak AZ 45° 48.42'  
Nail & Remon. tag in NE side 14" White Oak AZ 335° 77.79'  
Nail & Remon. tag in E side 13" White Oak AZ 185° 128.40'

Signed by *Kirk L. Van Order* Date 12-31-97  
Surveyor's Michigan License No. 23520

LIBR 0006 PAGE 234