

REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

<u>ALLEGAN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>14W</u>	<u>H-13 Valley</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 1994 DEC 16 AM 9:55
 FILED

Register of Deeds Stamp & File Number

I, Donald R. Pitts Jr., in a field survey on September 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.-Set Section Post
 6" Beech N.34°E. 13 Links
 10" Pine N.70°W. 34 Links
 Circa 1950-Allegan Co. Surveyor
 17" Oak S.W. 59.5'
 P. Pole S.W. 104.0'
 19" Oak S.S.E. 9.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 5/8" Iron in Mon. Box.
 Found 1/2" Iron w/Cap Kirk Van Order West 6.59'
 Pulled Iron and Set Standard Allegan Co. 3/4" X 24" Remon. Iron w/Red Cap #23520 in Mon. Box.
 Approved by the Allegan Co. Remon. Peer Group on April 12, 1994, and is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY

DATE APPROVED 4-12-94
 COUNTY REP [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Allegan Co. 3/4" X 24" Remon. Iron w/Red Cap #23520 in Mon. Box.
 H-1, T.1N., R.14W. Standard Allegan Co. 3/4" X 24" Remon. Iron w/Red Cap #23520 in Mon. Box West 6.59'
 Nail & Allegan Co. Remon. Tag in N.W. Side Power Pole S.55°W. 103.46'
 " " " " " in S.W. Side Power Pole S.15°E. 66.45'
 S.E. Corner House Foundation N.25°W. 202.64'



Signed by Donald R. Pitts Jr.
 Surveyor's Michigan License No. 25867

Date 21 SEPTEMBER 1994

1994 0005 PAGE 040