

REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

ALLEGAN
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 2N R 14W I-13
T _____ R _____ Valley
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1994 DEC 16 AM 9:55
 Register of Deeds
 ALLEGAN COUNTY MICHIGAN
Register of Deeds

FILED

Register of Deeds Stamp & File Number

I, Donald R. Pitts Jr., in a field survey on September 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.-Set corner post section 34 & 35
 20" Pine N.24°W 10 Links
 22" Pine N.56°E.31 Links

Circa 1900-Allegan Co. Surveyor Notes

Iron & Crockery
 24" Oak N.E. 65.8
 12" Oak N.W. 70'
 99" Cherry S. 48.6
 Pine Stump N.W. 20

Circa 1950 Allegan Co. Surveyor Notes

Iron & Crockery
 24" Oak N.E. 65.8'
 12" Oak N.W. 70.0'
 9" Cherry S. 48.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" Iron in Mon. Box.
 Found 3/4" Iron W/Cap Kirk Van Order West 9.42'
 Pulled Iron and Set Standard Allegan Co. 3/4" X 24" Remon. Iron W/Red Cap in Mon. Box.
 Approved by the Allegan County Remon. Peer Group on April 12, 1994, and is accepted as a careful and faithful perpetuation of the position of the original corner.
 Traversed 2651' East & 2641' West.


APPROVED REMONUMENTATION CORNER

P.A. 345 OF 1990
 ALLEGAN COUNTY

DATE APPROVED 4-12-94
 COUNTY REP. Kirk L. Van Order

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Allegan Co. 3/4" X 24" Remon Iron W/Red Cap #23520 in Mon. Box.
 I-1, T.1N., R.14W. Standard Allegan Co. 3/4" X 24" Remon Iron W/Red Cap #23520 in Mon. Box West 9.42'
 Nail & Allegan Co. Remon Tag in N.E. Side 30" Oak N.30°W. 69.98'
 " " " " " " " W. Side 12" Cherry N.10°E. 68.07'
 " " " " " " " N.E. Side Power Pole S.35°E. 44.29'



Signed by Donald R. Pitts Jr. Date 21 September 1994

Surveyor's Michigan License No. 25867

LIBER 0005 PAGE 041