

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

MAR 16 1993
 For corners in

Allegan
 County
 COMMISSIONER

Valley Township
 Located in: Corner Code #

1. Public Land Survey	T	<u>2N</u>	R	<u>14W</u>	<u>J-1</u>
	T		R		<u>N 1/4 Corner</u>
	T		R		<u>Section 2</u>
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

1993 DEC 17 PM 1:56
 J. A. Blanton
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Chris Marschall, in a field survey on July 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	3	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

AH Grush Survey				Van Ordre Survey			
Set "T" Iron with cap based on 1964 Ratekin Survey							
12" Hickory	N 17° W	80.51'		1991 Fd. Capped Iron			
24" Hickory	S 75° E	59.87'		22" Hickory SW	25.02'		
18" Hickory	S 22° W	24.93'		18" Hickory SSE	32.09'		
28" Hickory	S 68° W	66.80'		9" Elm NW	48.73'		
				S. Edge Asphalt Rd.	S 7.3'		

(SEE OTHER SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" Iron from above witnesses. Held as best evidence of perpetuation of true corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced "T" Iron with standard Allegan County Monument & Cap. Grouted top 3" K-13 N 90° E 2578.63' (K-13 Held for E & W)
 16" Penny cut Nail N side 14" Poplar "use as line" S09°46'56"E 112.53' (1/2" set Iron C.M. 18661 at S09°46'56"E 110.00') (1/2" set Iron C.M. 18661 at S09°46'56"E 40.00')
 16" Penny cut Nail NE side 8" Oak S 33° E 67.98'
 16" Penny cut Nail N side P.P. S 79° W 144.56'
 (Due to proposed Construction no Standard Monument and cap wer set at this location).
 Centerline E-W Bit. Road North 4'±
 Set Nail & Tag W. side 6" Ash N 29°E 56.21'
 Set Nail & Tag E. side 18" Walnut N 08°W 52.35'

SEE OTHER SIDE

Signed by Chris Marschall Date July 8, 1993
 Surveyor's Michigan License No. 18661

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

LIBER 004 PAGE 247

Page 1 of 2

Section A Continued:

LIBER 004 PAGE 248

Ratekins Files

Iron over Iron

17" Hickory SW 63.7'
14" Hickory S 31.5'
8" Walnut NNW 51.8'

NOTE: Allegan County Remon tag with 16d Duplex Nails were set on October 14, 1993
in line with the cut nails.