

REMONUMENTATION

APR 25 1995

COMMISSION

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>14W</u>	<u>J-13</u> <u>Valley Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1994 DEC 16 AM 9:55
 Roger A. Cobble
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald R. Pitts Jr., in a field survey on September 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.-Set section post
 9" Beech N.55°W. 33 Links
 28" Pine N.40°E. 38 Links


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No Corner Found
 Set Standard Allegan Co. 3/4" X 36" Remon Iron W/Red Cap #23520 Equidistant and on line from I-13 and K-13
 T.2N., R.14W., 7.77' East of J-1, T.1N., R.14W., in Mon. Box.
 Approved by the Allegan Co. Remon Peer Group on April 12, 1994, and is accepted as a careful and faithful reestablishment of the position of the original corner.
 Traversed 2657' East and 2641' West

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-12-94
 COUNTY REP. Richard Van Pelt

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Allegan Co. 3/4" X 36" Remon Iron W/Red Cap #23520 in Mon. Box.
 J-1, T.1N., R.14W. Standard Allegan Co. 3/4" X 24" Remon. Iron W/Red Cap #23520 in Mon. Box West 7.77'
 Nail & Allegan Co. Remon. Tag in S.W. Side 18" Oak S.30°E. 55.90'
 " " " " " " " " W. Side 10" Red Pine North 96.05'
 " " " " " " " " S.E. Side 16" Maple S.35°W. 72.64'



Signed by Donald R. Pitts Jr.
 Surveyor's Michigan License No. 25867

Date 21 September 1994

LIBER 0005 PAGE 042