

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN
 COMMISSION
 (County)

Located in: Valley Township
 Corner Code #

1. Public Land Survey	T <u>2N</u> R <u>14W</u>	<u>K-1</u>
	T _____ R _____	<u>NE Corner</u>
	T _____ R _____	<u>Section 2</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 17 PM 1:57
 Register of Deeds
 ALLEGAN COUNTY, MICH.
 J. L. E. [Signature]

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Chris Marschall, in a field survey on July 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


GL0 Set post 87.24 ch. N of 1, 2, 11, 12 and 6 L West of 35, 36
 Beech 24" S 45° W 17L
 Ironwood 6" S 57° W 27L
 Grush
 St. Sign S 32° E 31.62'
 Stop Sign S 20° E 38.85'
 P.P. S 68° W 67.47'
 16" Locust N 76° W 114.53'

Old Note
 Iron 4' W of 35, 36
 Elm 20" NE 41.8
 Elm 24" NE 40.4

(SEE OTHER SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Iron 0.05' South of the true Section line and 4.12' West of standard Corner K-13 Held as best evidence of perpetuation of true corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 7/8" x 22" Iron Pin 0.05' South of Township Line. Replaced it with Standard Allegan County Monument set on Township Line 4.12' West of the Heath Township Corner. Grouted Top 3".
 16 Penny cut Nail E. side 12" Hickory S 08° W 196.81'
 16 Penny cut Nail W. side 12" Walnut S 16° E 104.88'
 16 Penny cut Nail N. side P.P. S 65° W 67.50'
 16 Penny cut Nail SW side 14" Sasafrass S 42° E 66.17'
 K-13 East 4.12'
 Centerline E-W Bit. North 4.5'±
 Centerline N-S Gravel West 3'±

SEE OTHER SIDE

Signed by Chris Marschall Date July 8, 1993
 Surveyor's Michigan License No. 18661

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

Section A Continued:

AH Grush 1977 LCRC Filed April 22 3:50 p.m. 1977 L 3 P 145

Found 3/4" Diam. Solid Iron Bar
 and check with DA Ratekin Survey 1964

St. sign	S 32° E	31.62'
Stop sign	S 20° E	38.85'
P.P.	S 68° W	67.47'
16" Locust	N 76° W	114.53'

Van Order Survey 1991

Found Steel Rod

Centerline Stop Sign	SE 35.92
Centerline Tel. Pedestal	SW 51.30
P.P.	SW 67.47
Centerline Stop Sign	NW 63.60

From Ratekins Files

Old Notes

Iron

Elm 8"	S 13° W	77 1/2L
Elm 10"	N 30° E	65 L
Elm 8"	N 30° W	63' L

1" Iron 4' West of 35.36

P.P. SW 67.05

St. Sign SE 30.95

Centerline 24" Stump NE 43.00

Elm 20" NE 41.8'

Elm 24" NW 40.4'

NOTE: Allegan County Remon tag with 16d Duplex Nails were set on October 14, 1993
 in line with the cut nails.