

REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

ALLEGAN
(County)

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>2N</u> R <u>14W</u> | <u>K-13</u> |
| | T ___ R ___ | <u>Valley</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

1994 DEC 16 AM 9:55
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
Spencer A. Balthus

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____


A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald R. Pitts Jr., in a field survey on September 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessions and/or subsequent restoration:
- G.L.O.-Set post corner Section 35 & 36 Circa 1900-Allegan Co. Surveyor
 - 4" Beech N.88°W. 18 Links Stake
 - 14" Beech N.31°E. 43 Links 6" Oak S.W. 36.4'
 - 1887-Allegan Co. Surveyor, E.P. Waterman 8" Stump S.E. 31
 - Stake, No Witnesses
 - 1990-Allegan Co. Surveyor, Kirk L. Van Order
 - Found 5/8" Re-Rod in Mon. Box
 - 15" Red Pine S.E. 86.06' 26" White Oak N. 72.95'
 - 15" Burr Oak S.W. 140.22' 10" Maple N.E. 52.24'
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found Iron in Mon. Box.
 - Iron in Mon. Box West 5.78'
 - 15" Burr Oak S.W. 140.22'
 - 26" White Oak N. 72.95'
 - 10" Maple N.E. 52.24'
 - Pulled Iron and Set Standard Allegan Co. 3/4" X 24" Remon Iron W/Red cap #23520 in Mon. Box.
 - Approved by the Allegan Co. Remon Peer Group on April 12, 1994, and is accepted as a careful and faithful perpetuation of the position of the original corner.
- Traversed 2655' East & 2657' West
- C. Description of monument for corner and accessions established to perpetuate locating the position of the corner:
- Standard Allegan Co. 3/4" X 24" Remon Iron W/Red Cap #23520 in Mon. Box.
 - K-1, T.1N., R.14W. Standard Allegan Co. 3/4" X 24" Remon Iron W/Red Cap #23520 in Mon. Box West 5.78'
 - Nail & Allegan Co. Remon Tag in W. Side 26" White Oak N. 72.90'
 - " " " " " " S.W. Side 10" Oak N.35°W. 50.95'
 - " " " " " " S.E. Side 16" Burr Oak S.65°W. 140.22'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-12-94
 COUNTY REP. Kirk L. Van Order



Signed by Donald R. Pitts Jr. Date 12 Sept 1994
 Surveyor's Michigan License No. 25867

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1974
 REVISED MAY 14, 1975
 REVISED JAN., 1993