

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

MAR 16 1994

For corners in

Allegan
 COMMISSION
 (County)

Valley Township

Located in:

Corner Code #:

1. Public Land Survey	T <u>2N</u> R <u>14W</u>	L-1
	T _____ R _____	N $\frac{1}{2}$ Corner
	T _____ R _____	Section 1
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.

1993 DEC 17 PM 1:56

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Chris Marschall, in a field survey on July 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Old Notes "stake"	Van Order Survey 7/18/90
Stone (1/8 Post) S 25.90 ch.	Set capped Iron
Center of Section S	1 $\frac{1}{2}$ " Pipe W. (Heath Corner) 2.39'
Maple 4" N 20° E 70'	11" W. Pine ESE 14.12'
W. Maple 4" S 70° E 24'	7" Tulip N 8.75'
Stake 1/8 Post W 20.03 $\frac{1}{4}$ Ch.	10" Twin Maple WNW 11.08'
Stone NE corner E 40.06 $\frac{1}{2}$ Ch.	27" Maple WNW 17.31'
	Old Fence E & W & N

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 2.39' to L-1; L-1 N88°50'26"E 2633.594' to M-1. 2644.594'

Found $\frac{1}{2}$ " Rebar with KVO Cap from above witnesses



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard 30" x 3/4" Steel Pin in place of 1/2" Iron Rebar KVO Cap 23530
 L-1
 16" Penny cut Nail E side 10" Maple N 07° E 32.87'
 16" Penny cut Nail N side 14" Pine S 88° E 14.11'
 16" Penny cut Nail N side Twin 8-12 Maple N 69° W 11.03'
 16" Penny cut Nail NE side 14" Ash N 32° W 33.32'
 L-13 West 2.40'

Note: Allegan County Remon tag with 16d Duplex Nails were set on October 14, 1993 in line with the cut Nails.

Signed by Chris Marschall Date July 8, 1993
 Surveyor's Michigan License No. 18661

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1982