

MAR 07 2000

FILED

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

00 FEB -1 AM 8:35

SECTION

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T. 2N R. 13W	A-2
WEST 1/4 CORNER SECTION 6, ALLEGAN TOWNSHIP	T. 2N R. 14W	M-2 ✓
EAST 1/4 CORNER, SEC. 1, VALLEY TOWNSHIP	T. R.
	T. R.
2. Property Controlling in section	S. T. R.
	S. T. R.
3. Miscellaneous Property in Sec.	S. T. R.
4. Lot No., Recorded Plat.		
5. Private Claims.		

Raymond E. Moored
REGISTER OF DEEDS
ALLEGAN COUNTY

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		-5-		4		-3-		2		-1-		
3													
4	7		-8-		9		-10-		11		-12-		
5													
6	18		-17-		16		-15-		14		-13-		
7													
8	19		-20-		21		-22-		23		-24-		
9													
10	30		-29-		28		-27-		26		-25-		
11													
12	31		-32-		33		-34-		35		-36-		
13													

I, Raymond Moored in a field survey on Nov. 7, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED Nov. 9, 1999
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON IN MON. BOX PER WITNESSES IN NO. 4 ABOVE. ALL WITNESSES REMAIN.
DISTANCE TO A-3 = 2844.34' (RATEKIN = 2844'); DISTANCE TO A-2 = 2962.33' (RATEKIN = 2962.60') PULLED IRON AND SET STANDARD ALLEGAN COUNTY REMON. IRON W/ CAP IN MON. BOX.

ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON Nov. 9, 1999

TOTAL DISTANCE TRAVERSED = 2962.33' ON ROAD

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMON. IRON WITH CAP IN MON. BOX

- CAMPING SIGN N80E 18.02' (TO WEST EDGE OF SIGN POST)
- FD. P.K. IN S. SIDE POWER POLE N90E 113.65'
- FD. NAIL IN N. SIDE GUARD RAIL POST S90W 17.53'
- SET NAIL & TAG IN SE SIDE 12" SASSAFRAS N40E 58.95'
- SET NAIL & TAG IN NW SIDE 13" SASSAFRAS N25E 103.84'
- FD P.K. NAIL IN NW SIDE POWER POLE N34E 218.31'

Raymond Moored Date 11/10/99

Surveyors License No. 26463



RF

PLAT &
SECTION

MAR 07 2000

SECTION

**A-2, ALLEGAN TOWNSHIP, ALLEGAN COUNTY
T.2N., R.13W.**

**M-2 VALLEY TOWNSHIP, ALLEGAN COUNTY
T2N, R14W**

A. Description of original monument and accessories and/or subsequent restoration:

1. G.L.O. (A-2)
THIS POSITION NOT ESTABLISHED BY G.L.O.
G.L.O. (M-2)
NORTH ON EAST SIDE SEC. 1, 40.00 CHS. SET QR. SEC. POST
BEECH 5 S37W 23
BEECH 18 N67W 25
2. A.C.R.C. RECORDS
W. 1/4 POST, SEC-6, ALLEGAN, IRON
P.P. NE 217.95'
P.P. ENE 113.7'
FE COR ESE 33.1'
10" MAPLE SE 44.9'
15" MAPLE SW 49.6'
SW CONC BLK FND NE 128.4'
NE COR OF OLD
BARN STONE FND SW 238.5'
JOG 4' S TO E 1/4 POST SEC-1, VALLEY
3. OLD COUNTY SURVEYOR'S RECORDS (BLACK BOOK)
W 1/4 POST, SEC-6, ALLEGAN, IRON
16" MAPLE SW 49.6'
12" MAPLE SE 45'
FE COR SE 33.1'
A-3 TO A-2 = 2644'
A-3 TO A-1 = 5250'
4. 70'S RATEKIN WITNESS CARD
W 1/4 POST SEC-6 ALLEGAN
1" IRON IN C/L ROAD
P.K. S. SIDE P.P. E 113.70'
CAMPING SIGN N80°E 18.02'
NAIL IN SDE
GUARD POST S80°W 17.36'
5. 20, JUNE '74 D.A. RATEKIN, C.S., ACT 132 SURVEY, S.W. 1/4 SEC-6
W 1/4 COR. IRON
IDENTICAL WITNESSES TO THOSE ON CARD
6. 29, APRIL '81 D.A. RATEKIN, C.S., SURVEY IN NW 1/4 SEC-6
SHOWS A-2, NO WITNESSES
A-2 TO A-1 = 2962.63'
7. '90 WIGHTMAN-MOORED, SECTION BREAKDOWN SHEET
A-2 NO WITNESSES
A-3 TO A-2 = 2643.93'
A-2 TO A-1 = 2962.38'
P.O.T. BETWEEN A-1 & A-2 (1/2" PIPE 1150.93' SOUTH OF A-1)

LEROU 07 PART 14 U

