

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN

(County)

Located In:

Corner Code //

1. Public Land Survey	T 2N	R 14W	H8
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S 23	T 2N R 14W	10
	S 23	T 2N R 14W	11
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, **GARY C. BILOW**, in a field survey on **April 30, 1991**, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (H-8) CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. FOUND NO SUBSEQUENT RECORD.
- (10) CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. FOUND NO SUBSEQUENT RECORD.
- (11) CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. FOUND NO SUBSEQUENT RECORD.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(H-8) FOUND 1" IRON BAR IN MONUMENT BOX AND DETERMINED SAME TO BE ON A STRAIGHT LINE CONNECTING 6-8 WITH 1-8. NORTH 1/4 CORNER OF SECTION 22 (H-7) NOW FALLS IN LAKE ALLEGAN. I MADE NO FURTHER ATTEMPT TO VERIFY THIS CORNER AND IT IS BEING RECORDED HERE FOR INFORMATION ONLY.

(10) FOUND AN OLD AXE HEAD BURIED VERTICALLY ABOUT 8" BELOW GROUND SURFACE 4' EAST OF CORNER POSITION. FOUND NO OTHER EVIDENCE OF PRIOR MONUMENTATION. ESTABLISHED CORNER MIDWAY AND ON A STRAIGHT LINE BETWEEN 1-9 AS RECORDED THIS DATE AND 1-8 AS APPEARS IN LIBER 1, PAGE 368 OF LAND CORNER RECORDS. MONUMENTED THE CORNER POSITION WITH AN UNCAPPED 1" DIAMETER IRON BAR SET FLUSH.

(11) FOUND NO EVIDENCE OF PRIOR MONUMENTATION AT THIS POSITION BUT NOTED THAT APPROXIMATE CORNER POSITION IS MARKED BY THE SE CORNER OF A SCOTCH PINE PLANTATION AND THE SW CORNER OF A RED PINE PLANTATION. ESTABLISHED CORNER AT THE INTERSECTION OF STRAIGHT LINES CONNECTING CORNERS 8 WITH 15 AND 10 WITH 12, ALL AS RECORDED THIS DATE. AT THE POSITION FOR THE CORNER, I PLACED A 1/2"x36" REBAR ENCASED IN A 4" DIAMETER CONCRETE CYLINDER CAPPED WITH A CAST ALUMINUM MICHIGAN DEPARTMENT OF NATURAL RESOURCES TABLET.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H-8) FOUND 1" IRON BAR IN MONUMENT BOX NORTH 2.5' CENTERLINE OF BITUMINOUS SURFACE OF MONROE ROAD; N40W 45.30' SET NAIL AND MICHIGAN DEPARTMENT OF NATURAL RESOURCES TAG IN WEST FACE POWER POLE; S32W 36.88' SET NAIL AND MDNR TAG IN WEST FACE 18" W. OAK; S20E 46.23' SET NAIL AND MDNR TAG IN WEST FACE 12" W. PINE; WEST 42' CENTERLINE OF DRIVEWAY TO NORTH.

(10) SET 1" DIAMETER IRON BAR N10E 13.71' SET NAIL AND MICHIGAN DEPARTMENT OF NATURAL RESOURCES TAG IN WEST FACE 8" W. OAK; S05E 29.41' SET NAIL AND MDNR TAG IN NORTH FACE 8" AND 10" TWIN OAK; S75W 68.02' SET SET NAIL AND MDNR TAG IN SOUTH FACE OF 8"-9"-10" TRIPLE OAK; N55W 35.61' SET NAIL AND MDNR TAG IN SOUTH FACE OF 12"-8"-8" TRIPLE OAK; EAST 34' CENTERLINE OF N-S TRAIL.

(11) SET CONCRETE MONUMENT WITH MDNR CAP N65W 20.48' SET NAIL AND MDNR TAG IN NE FACE 7" R. PINE; N60E 29.60' SET NAIL AND MDNR TAG IN NW FACE 12" W. PINE; SOUTH 25.60' SET NAIL AND MDNR TAG IN EAST FACE 6" TWIN B. OAK; S20W 19.88' SET NAIL AND MDNR TAG IN WEST FACE 7" TWIN W. OAK. BLAZED ABOVE NOTED TREES AT BASE AND 8H.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Gary C. Bilow

Date 9-30-91

Surveyor's Michigan License No. 26453

