

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>26</u> T. <u>2</u> N. <u>14</u> E. R. <u>14</u> W.		<u>I-10, J-9, J-10</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>I-10 3/4" pipe. South side 115th and on $\frac{1}{2}$ of trail to the north. S 10° W 22" Oak 45.6' PK, East Side N 35° W 6" Pine 37.7' PK, East Side N 20° E 12" Oak 50.5' PK, West Side</p>	<p>J-9 Set by projection of bearing and distance between C 1/4 cor. sec. 23 and S 1/8 cor. of N-S 1/4 line, sec. 23 as recorded by D.A. Patekin and Assoc.</p>	<p>J-10 Set at the intersection of N-S and E-W 1/4 lines.</p>
---	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>I-10 Found 3/4" pipe N 22° W 13" R. Oak 50.48' Spike N 35° W 7" J. Pine 37.65' Spike S 11° W 22" W. Oak 46.33' Spike N 89° E 24" B. Oak 89.55' Spike</p>	<p>J-9 Set 1" pipe. Cap #18655 West $\frac{1}{2}$ of trail 22' S 35° E 14" W. Oak 43.66' Spike S 25° W 19" W. Oak 29.99' Spike N 29° E 28" W. Oak 45.77' Spike S 75° E 12" Twin W. 14.77' Spike Oak</p>	<p>J-10 Set concrete monument with aluminum cap. South $\frac{1}{2}$ road 32' N 22° W 25" Twin Oak 64.40' Spike N 65° W 8" J. Pine 10.48' Spike S 40° E 11" J. Pine 6.67' Spike N 07° E 26" R. Oak 67.70' Spike</p>
---	--	--

R6# 204

R6# 305

R6# 200

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 1-30-78
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655