

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in ALLEGAN COUNTY Located In: Corner Code #

1. Public Land Survey T..2N R.15W..... * A-1..CLYDE TWP
 SEC COR COMMON T..3N R.15W..... A-13.MANLIUS TWP
 T2N, R15 & 16, T3N, R15 & 16W T..2N... R.16W..... M-1..GANGES TWP
 T..3N... R.16W..... M-13.SAUGATUCK

2. Property Controlling in Section S.....T..... R.....
 S.....T..... R.....

3. Miscellaneous Property in Sec. S..... T..... R.....
 S..... T..... R.....

4. Lot No....., Recorded Plat.....
 5. Private Claims.....

97 JUN 22 PM 1:22
 REGISTERED ALLEGAN COUNTY
 Register of Deeds Stamp & File Number

I, RAYMOND MOORED, in a field survey on OCT, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

SEE SHEET 2 OF 2 FOR CORNER HISTORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" ROD IN MON BOX PER ACCESSORIES ABOVE: RATEKIN DIST A-1 TO B-1 2126.16'
 MEASURES A-1 TO B-1 2126.36'
 REPLACED IRON WITH 3/4" X 24" ALLEGAN CO. REMONUMENTATION IRON AND CAP AND ACCEPTED IT AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.
 APPROVED BY ALLEGAN COUNTY REMON PEER GROUP 11-12-96.
 TRAVERSED 2126.36' FEET OF ROAD.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-12-96
 COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN MONUMENT BOX
 -NAIL & TAG IN E SIDE 10" PINE N45°E 53.19'
 -S.W. HOUSE COR. N25°E 91.64'
 -NAIL & TAG IN E. SIDE BEECH TREE CLUSTER N 5°E 51.60'
 -NAIL & TAG IN E. SIDE TELE. POLE S45°W 77.50'
 B-1 T.2N., R.15W., EAST 2126.36'



Signed by *[Signature]* Date 12.13.96
 Surveyor's Michigan License No. 26463

GOVERNMENT CORNER HISTORY

SEC. COR. COMM. TO
T.2N., R.15W. & R.16W./T.3N., R.15W. & R.16W.

A-1, A-13, M-1, M-13

G.L.O (LYON)	1831	W. ON S. LINE, SEC. 31, 79.45 CHS TO RANGE LINE, 69 LKS NORTH OF TEMP. COR. SET POST CORNER TOWN 2 & 3 NORTH, RANGE 15 & 16 WEST.
		SUGAR 28 S27E 40
		BEECH 36 N23W 8
MAC DOUGALL		1900'S CALLS FOR STONE
		MAPLE 14" S.W. 30
RATEKIN	1970'S	INDICATE CORNER WITH MEASUREMENTS TO ADJACENT CORNERS, BUT NO WITNESSES
MITCHELL		SURVEYS 1977-1992
		T.C.B. S.W. 77.1'
		TELE POLE S.E. 75.7'
		T.C.B. N.W. 71.75'
VAN ORDER		FOUND 1" STEEL ROD IN MON BOX C/L
		T.C.B. N.W. 71.45'
		NAIL IN SE SIDE TP S.W. 77.49'
		NAIL IN NE SIDE PP S.E. 75.76'
		NAIL IN SE SIDE PP N.E. 109.13'