

SURVEY &  
RECORDS

FILED

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FEB -1 AM 8:37

SECTION

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>15W</u>	<u>A-5</u> <u>Clyde Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

*Joyce A. Carter*  
REGISTER OF DEEDS  
ALLEGAN COUNTY MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Kirk L Van Order, in a field survey on Dec 16 & Dec 22, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-5  
(1) GLO post established by U.S. Deputy Surveyor L. Lyon, July 17, 1831  
West between Sections 7 & 18  
73.41 to W. boundary 68 links S. of post  
Set post cor. Section 7 & 18  
Tam 14 N83E 11 links  
Do 15 S17E 31 links  
(continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5  
Fd. standard A. C. Remon. monument and following accessories as listed in No. 9. Fd. point falls 0.92' East of range line. Set standard A. C. Remon. monument on range line and 0.92' West of found point which was left in place and red cap removed.  
And is accepted as a careful and faithful perpetuation of the position of the original corner.  
Peer group approved Dec. 28, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5  
Standard Allegan Co. Remon. monument (3/4" x 24" steel rod w/red cap #23520)  
3/4" steel rod  
Nail & Remon. tag NW side power pole  
Nail & Remon. tag in S side Zone 1 sign post  
Nail & DNR tag in SE side 9" cherry  
C/L S. end 5' dia. CMP  
C/L N. end 5' dia. CMP  
M-5, T.2N., R.16W.  
C/L Gravel road

East	0.92'
S.80°W.	50.44'
N.40°W.	41.70'
N.55°E.	58.48'
S.35°W.	14.90'
N.5°W.	30.68'
N.1°W.	44.88'
North	8.5'

Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 23520

Date 12 28 1999

APPROVED REMONUMENTATION CORNER

P.A. 74 OF 1990

ALLEGAN COUNTY

DATE APPROVED DEC 28 1999

COUNTY REP. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1995



