

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

00 FEB -1 11 8:37

SECTION

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>15W</u>	<u>A-11</u>
	T ___ R ___	<u>Clyde Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Joyce L. Castle
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 Register of Deeds Stamp & File Number

LIBERO 007 PAGE 190

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk L. Van Order in a field survey on Dec 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-11
(1) GLO post established by U.S. Deputy Surveyor L. Lyon in 1831 West between Sections 30 & 31 75.38 to W. boundary 5 links N. of post, where set Post cor. Section 30 & 31 Beech 14 N21E 24 links Do 10 S75E 6 links (continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11
Fd. standard Allegan Co. Remon. monument on range line and the following accessories:
N35E 96.66', Nail & DNR tag 16" (now 18") cherry
S16W 108.15' (M - 108.10'), Nail & DNR tag 24" (now 25") maple
South 3.32' (M - 3.31'), Corner M-11, T.2N., R.16W.
S80W 41.52' (M - 41.56'), Nail & DNR tag 7" (now 11") pine
S70E 47.84' (M - 47.83'), Nail & DNR tag in 10" (now 12") cherry
And is accepted as a careful and faithful perpetuation of the position of the original corner. Peer group approved Dec. 28, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11
Standard Allegan Co. Remon. monument (3/4" x 24" steel rod w/red cap #23520)
Nail & DNR tag in SE side 18" cherry N35°E 96.66'
Nail & DNR tag in N side 12" cherry S70°E 47.83'
Nail & DNR tag in N side 11" pine S80°W 41.56'
Nail & DNR tag in W side 25" maple S16°W 108.10'
Nail & Remon. tag in E side 31" maple S25°W 114.16'
M-11, T.2N., R.16W. South 3.31'

Signed by [Signature]
Surveyor's Michigan License No. 23520

Date 12-10-99



APPROVED REMONUMENTATION CORNER
P.A. 343 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 28, 1999
COUNTY REP. [Signature]

MAR 07 2000

SECTION

LIBERO 007 PAGE 191

Section A (continued from Page 1)

A-11

Clyde Twp., T.2N., R.15W.

- (2) George Mitchell survey dated Nov. 10, 1978, Job No. 78-409 shows this corner but does not state what was found
8" pine SW 82.45'
14" cherry E,SE 27.20'
6" cedar NW 54.45'
M-11 N 3.3'
- (3) Wightman-Moored, Inc. info show 1" iron 3.30' North of corner M-11
- (4) Thomas W. Benson, DNR Surveyor, info dated Jan. 9, 1996
Found 5/8" rerod and none of the above accessories
GLO distance to corner M-11, T.2N., R.16W. checked. Replaced 5/8" rerod with standard Allegan Co. Remon. 3/4" x 24" iron with red cap 23520
N35E 96.66', Nail & DNR tag 16" cherry
S16W 108.15', Nail & DNR tag 24" maple
South 3.32', Corner M-11, T.2N., R.16W.
S80W 41.52', Nail & DNR tag 7" pine
S70E 47.84', Nail & DNR tag 10" cherry
North 2645.04', A-10, T.2N., R.15W.
South 2634.67', A-12, T.2N., R.15W.