

RECORDED & INDEXED  
MAR 07 2000

FILED

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

00 FEB -1 AM 8:37

For corners in SECTION  
Allegan (County) Located In: Corner Code #

1. Public Land Survey T2N R15W B-5  
T R  
T R North 1/4 corner  
T R Section 18  
2. Property Controlling S T R Clyde Twp.  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

*Joyce A. ...*  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
Register of Deeds Stamp & File Number

RECORDED & INDEXED

I, Steve Lampen, in a field survey on December 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	18	17	16	15	14	13							
6													
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
B-5  
GLO - 1831 - C. Britain  
Set post  
Tamarack 15 S 2 W 39  
Cedar 15 N 5 W 38  
No other records recovered

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
B-5 Found 1/2" iron. Pulled iron and set Standard Allegan County 3/4"x24" remonumentation iron with red cap #23520.

Approved by the Allegan County Remonumentation Peer Group on December 28, 1999, and is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED DEC 28, 1999  
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
B-5 Standard Allegan County 3/4"x24" remonumentation iron with red cap #23520  
Azimuth = Michigan State Plane grid direction

Centerline E & W gravel road	180°	6±
Centerline ditch to N	270°	6.1'
Railroad tie fence post with remonumentation tag NE side	304° 05'	38.89'
Railroad tie fence post with remonumentation tag NE side	319° 52'	27.06'
Set 1/2" diameter steel rod on N & S 1/4 line, Sec. 18, T2N, R15W	179° 27' 25"	24.57'
Found steel bar	358° 05'	33±
Set 1/2" diameter steel rod	235° 40'	41.77'



Signed by Steven Lampen Date DECEMBER 31, 1999  
Surveyor's Michigan License No. 37279