

SURVEY & REMONUMENTATION

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

APR 25 1995

For Corners in
Allegan
COMMISSION

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
James A. Collette

1994 DEC 16 AM 9:54

FILED

| | | |
|---------------------------------------|----------------------------|---------------|
| | Located in: | Corner Code # |
| | Clyde Township | |
| 1. Public Land Survey | T <u>2</u> N R <u>15</u> W | B-13 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, George J. Mitchell, in a field survey on December 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 13 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

B-13 L. LYON 1831 SET POST 40 CHAINS WEST
BEECH 5 N67E 30 LKS
BEECH 4 N78W 20 LKS

NO OTHER HISTORY AVAILABLE ON THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 FOUND 5/8" IRON THAT HAD BEEN SET ON THE TOWNSHIP LINE AT THE PRORATED GOVERNMENT DISTANCE BETWEEN A-13 AND C-13. THE CORNER LOCATION WAS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

MEASURED 2391.22' WEST TO A-13 AND 2643.69 FEET EAST TO C-13

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-29-94
COUNTY REP. Rich L. Van Orsdel



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 REPLACED IRON WITH 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP.

| | | |
|--|----------|---------|
| A.C. remon tag & nail in North side of 8" tw. Oak | AZ. 90° | 3.71' |
| A.C. remon tag & nail in West side of Power Pole | AZ. 105° | 181.62' |
| A.C. remon tag & nail in East side of 24" triple Oak | AZ. 180° | 123.04' |
| A.C. remon tag & nail in North side of 24" Oak | AZ. 90° | 21.26' |
| Lee Township Corner B-1 | AZ. 90° | 197.28' |

Signed by George J. Mitchell Date December 12, 1994
Surveyor's Michigan License No. 1961B

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1973
REVISED JAN., 1983

LIBR 0005 PAGE 015