


**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in <u>ALLEGAN COUNTY</u>	Located In:	Corner Code #
1. Public Land Survey SEC. COR. COMM. TO SEC. S 5 & 6, T2N, R15W	T..2N R..15W T..... R..... T..... R..... T..... R.....	....C-1...CLYDE TWP
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....	.....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....	.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

  
 97 JAN 22 PM 1:22  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY  
 FILED

Register of Deeds Stamp & File Number

I, RAYMOND MOORED, in a field survey on OCT, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 11-13-96  
 COUNTY REP. [Signature]


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND SQUARE BOLT IN MON BOX PER RATEKIN WITNESSES ABOVE. JOG DISTANCE TO C-13, T.3N., R.15W. MEASURED 277.70'. RATEKIN WITNESS CARD MEASURED 278'. CORNER AS FOUND IS 0.30' SOUTH OF RANGE LINE ESTABLISHED BY B-13 & C-13. ACCEPTED EAST-WEST POSITION AND MOVED POSITION NORTH 0.30' TO RANGE LINE. ACCEPTED POSITION AS A CAREFUL & FAITHFUL PERPETUATION OF THE ORIGINAL CORNER. SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMON IRON AND CAP. APPROVED BY ALLEGAN COUNTY REMON PEER GROUP 11-12-96. TRAVERSED 5,044 FEET ON ROAD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP

-NAIL & TAG IN W. FACE OF TELE. POLE	N20°E	34.88'
-NAIL & TAG IN E. SIDE OF TELE. POLE	S45°E	58.97'
-NAIL & TAG IN W. FACE TELE. POLE	S25°W	73.60'
-NAIL & TAG IN W. SIDE 24" MAPLE	S70°E	67.50'
C-13 T.3N., R.15W. EAST	277.70'	
B-13 T.3N., R.15W. WEST	2367.27'	



Signed by Raymond Moored Date 12/13/96  
 Surveyor's Michigan License No. 26463

GOVERNMENT CORNER HISTORY

SECTION COR. COMM. TO SEC'S 5 & 6  
TOWN 2 NORTH, RANGE 15 WEST

C-1

LYON (GLO)		NORTH 84.91 TO RANGE LINE 496 LINKS (327.36') WEST OF POST SET POST COR SECTIONS 5 & 6 SUGAR 8                    S45E 29 BEECH 14                   S40W 12
CHICHESTER	1866	SET LONGISH STONE WITH X ON TOP AND NORTH SIDE OF CORNER. NORTH LINE LONG BY 103 LINKS
GARDNER	1874	STONE WITH X FOR CORNER
MACDOUGALL		BLACK WITNESS BOOK. SEC 5 CLYDE IRON FOR CORNER NE COR. HOUSE           SW    90.1' MAPLE 24                   NW    113.7'
RATEKIN		WITNESS CARD SQUARE BOLT IN MON BOX BOX IS 1' NORTH OF C/L E-W HIGHWAY BOX IS ON C/L ROAD SOUTH UTILITY POLE            N5E    35.45' TO NAIL UTILITY POLE            S25E   59.0' TO NAIL UTILITY POLE            S25W   73.18' TO NAIL
VAN ORDER		WITNESS CARD WITNESSES SAME AS RATEKIN
MIDDLETON		LIBER 2, PAGE 274 CORNER SAME AS RATEKIN & VAN ORDER ABOVE

USED IN SURVEYS BY RATEKIN, KIRK VAN ORDER, AND WIGHTMAN  
MOORED.