

RF

MAR 07 2000

FILED

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

00 FEB -1 / 11 8:38

SECTION

For corners in

Allegan
(County)

Located in:

Corner Code #

- 1. Public Land Survey T2N R15W C-8
T R
T R East 1/4 corner
T R Section 19
Clyde Twp.
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Joyce A. Britain

REGISTER OF DEEDS
ALLEGAN COUNTY MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Steve Lampen, in a field survey on December 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-8
GLO - 1831 - C. Britain
Set post
Hemlock 5 S 26 W 24
Beech 11 N 54 E 16

No other records recovered

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 Found 3/4" iron. In centerline of road intersection to North, South, East and West set standard Allegan County red Remonumentation cap #23520 on old iron.


Approved by the Allegan County Remonumentation Peer Group on December 28, 1999 and accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED 020.28.1999
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8
Standard Allegan County red Remonumentation cap #23520 on found 3/4" iron
Azimuth = Michigan State Plane grid direction
18" Ash with remonumentation tag SW side 146° 50' 108.79'
12" Pine with remonumentation tag NW side 53° 21' 78.56'
12" Pine with remonumentation tag NW side 40° 48' 73.84'
10" Pine with remonumentation tag E side 326° 19' 56.99'



Signed by *Steven Lampen*

Date DECEMBER 31, 1999

Surveyor's Michigan License No. 37279