

SURVEY & REMONUMENTATION

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

APR 25 1995
For Corners in
Allegan

COMMISSION

1. Public Land Survey

Located In: Corner Code ##

Clyde Township

T 2 N R 15 W C-13

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds
 ALLEGAN COUNTY MICHIGAN
 George J. Mitchell

1994 DEC 16 AM 9:54

FILED

Register of Deeds Stamp & File Number

I, George J. Mitchell, in a field survey on December 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-13	L. LYON 1831 SET POST AT 80 CHAINS	RATEKIN WITNESS CARD FD 1" IRON
	HEMLOCK 12 N66E 42 LKS	8" CEDAR POST WNW 40.8' GONE
	HEMLOCK 7 N75W 30 LKS	10" TW CHERRY NW 44.2' CK 94
		10" CHERRY NE 79.0' CK 94
		POWER LINE SOUTH 53.2' CK 94
		LEE TWP COR EAST 197.39' CK 94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 FOUND 1" IRON 12" DEEP AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-29-94
COUNTY REP. George J. Mitchell



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13	REPLACED POST WITH 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP.	
	A.C. remon tag & nail in West side of Power Pole	AZ. 107° 190.30'
	A.C. remon tag & nail in NE side of 18" quad Cherry	AZ. 307° 45.15'
	A.C. remon tag & nail in East side of 24" Oak	AZ. 189° 129.75'
	Center wires on Power line	AZ. 180° 53.20'
	Lee Township Corner C-1	AZ. 90° 197.39'
	Center of North-South asphalt road	AZ. 90° 99.0'

Signed by George J. Mitchell Date December 12, 1994
Surveyor's Michigan License No. 19618

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBR:0005 PAGE 016