

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

98 JAN 21 PM 1:20
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 FILED

For Corners in ALLEGAN COUNTY	Located In:	Corner Code #
1. Public Land Survey NORTH 1/4 COR SEC. 4 CLYDE TWP.	T..2N R..15W T..... R..... T..... R..... T..... R.....F-1.....
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RAYMOND MOORED, in a field survey on SEPTEMBER 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 9-9-97
COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" PIPE IN MON. BOX PER #3,4, & 8 ABOVE COR. FOUND IS 0.05' NORTH OF LINE BETWEEN E-13 AND F-13.
SET 3/4" X 24" ALLEGAN CO REMON IRON W/ REMON CAP ON TOWNSHIP LINE BETWEEN E-13 AND F-13 AT MEASURED DISTANCE FROM F-13.
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.


APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON 9-9-97

TOTAL LINEAL FEET OF ON ROAD TRAVERSING= 2655.92'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN MON. BOX
- NAIL & TAG IN W SIDE P. POLE S30E 100.30'
- NAIL & TAG IN NW SIDE P. POLE S25W 66.60'
- NAIL & TAG IN NW SIDE P. POLE N30W 56.40'
- NAIL & TAG IN E SIDE P. POLE N30E 64.80'
- ON C/L ROAD TO SOUTH
- C/L M-89 HWY SOUTH 9'
- S 1/4 COR SEC. 33 (F-13) EAST 183.87'

Signed by Raymond Moored Date 12/17/97
Surveyor's Michigan License No. 26463



GOVERNMENT CORNER HISTORY
 NORTH 1/4 CORNER OF SECTION 4
 TOWN 2 NORTH, RANGE 15 WEST

F-1

PART A: 1. CORNER NOT ESTABLISHED BY G.L.O.

2. D. RATEKIN COUNTY SURVEYOR WITNESS CARD
 7.82' NORTH OF STA. 55 + 93.55 (MDOT - 1946)
3. D. MIDDLETON LCRC REC. L.2, PG. 272 DATE 2-11-74
 FOUND 1/2" PIPE IN MON BOX
 BOX IS 8' +/- N OF C/L E - W HIGHWAY
 P. POLE N15°W 53.38' TO NAIL
 P. POLE N25°E 64.95' TO NAIL
 P. POLE S15°W 86.58' TO NAIL
4. W.Q. SMITH SURVEY REC. IN L. 845, PG. 539.40 DATE 2-20-74
 SURVEY REC. IN L. 845, PG. 543.44 DATE 2-20-74
 SURVEY REC. IN L. 845, PG. 543-44 DATE 2-20-74
 SAME INFO AS NO. 3 ABOVE
5. J.H. DILLINGHAM SURVEYS DATED 5-17-76, 8-18-78
 SAME INFO AS NO. 3 ABOVE
6. JOHN CLAPP SURVEY REC IN L. 1015, PG 714
 SAME INFO AS NO. 3 ABOVE
7. RAYMOND MOORED SURVEY DATED 5-27-83
 USED CORNER, NO WITNESSES
8. K. VAN ORDER SURVEY DATED 10-31-83
 FOUND 1/2" PIPE IN MON BOX
 BOX IS 8' +/- N OF C/L E - W HIGHWAY
 P. POLE N15°W 56.38' TO NAIL
 P. POLE N25°E 64.95' TO NAIL
 P. POLE S15°W 86.58' TO NAIL
9. K. VAN ORDER SURVEY, DATED 6-2-87 AND 9-12-89
 SAME INFO AS NO. 8 ABOVE
10. MITCHELL SURVEYS WITNESS SHEET 1995
 SAME INFO AS NO. 8 & 9 ABOVE
11. HOLLAND ENGINEERING WITNESS SHEET
 SAME INFO AS NO. 8 & 9 ABOVE