

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98 JAN 21 PM 1:20
REGISTER OF DEEDS
ALLEGAN COUNTY
FILED

For Corners in ALLEGAN COUNTY	Located In:	Corner Code #
1. Public Land Survey SEC COR COMMON TO SEC. 3 & 4 CLYDE TWP.	T..2N R..15W T..... R..... T..... R..... T..... R.....	...G-1.....
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

I, RAYMOND MOORED, in a field survey on SEPTEMBER 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 9-9-97
COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND RR SPIKE W/PX PER #8 AND #14 ABOVE. FOUND FALSE CORNER E. 6.39'. MEASURED JOG FROM RR SPIKE TO G-13 OF 129.09' AGREES W/ WATERMAN IN 1887 (129.36'). GLO NOTES DO NOT GIVE JOG DISTANCE BUT GLO MAP LISTS JOG DISTANCE OF 2.12 CH.=139.92'. WATERMAN FOUND GOVT STAKES AT G-1 AND G-13 IN 1887 AND MEASURED JOG AT 129.36'.-CORNER IS 0.21' S OF TOWNSHIP LINE.


ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON 9-9-97
TOTAL LINEAL FEET OF ON ROAD TRAVERSING= 2658.58'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
- CORNER IS 5 FEET WEST OF C/L ROAD TO SOUTH
- NAIL & TAG 6' HIGH IN SW SIDE P. POLE N40W 57.42'
- NAIL & TAG 6' HIGH IN NW SIDE P. POLE N50E 82.53'
- NAIL & TAG 6' HIGH IN SW SIDE P. POLE S40E 74.35'
- IRON EAST 6.39'
- SE COR SEC 33 MANLIUS (G-13) EAST 129.09'

Signed by Raymond Moored Date 12/17/97
Surveyor's Michigan License No. 26463



GOVERNMENT CORNER HISTORY
SECTION CORNER COMMON TO SECTIONS 3 & 4
TOWN 2 NORTH, RANGE 15 WEST

G-1

- PART A: 1. G.L.O. L. LYON D.S., 1831 NORTH BETWEEN SEC'S 3 & 485.33 CH.
INTERSECTED N. BNDRY. SET POST COR TO SEC'S 3 & 4.
PIN OAK 12 S67W 169
PINE 36 S2E 540
NOTE: NO GOVT JOG DISTANCE LISTED IN NOTES. GOVT MAP OF CLYDE
TWP. SHOWS JOG DISTANCE OF 2.12 CH'S. - 139.92').
2. E. P. WATERMAN, DEP. CO. SURVEYOR, SURVEY DATED 9-1-5-1887
SURVEY OF SEC. 3 BY GENERAL APPLICATION
NO WITNESSES. FOUND OAK STAKE.
GOVT STAKE AT G-13, T3N, R15. MEASURED JOG TO
G-13 AT 1.96 CH'S (129.36').
3. D. RATEKIN CO. SURVEYOR WITNESS CARD - NO DATE
1" IRON
P. POLE N45W 61.20'
ST. SIGN N45E 48.15'
P. POLE N45E 75.44'
4. D. RATEKIN SURVEYS DATED 8-11-69 AND EARLY 1970'S (NO DATE SHOWN).
USED CORNER, NO WIT'S. SHOWN
5. D. RATEKIN LCRC REC. IN L. 2, PG. 60 DATE 11-28-72
SAME AS IN NO. 3 ABOVE
6. D. RATEKIN SURVEY DATED 11-29-72
USED CORNER, WIT'S SAME AS NO. 3 ABOVE
7. D. MIDDLETON LCRC REC. IN L. 2, PG. 273 DATE 2-11-74
SET CORNER AT JOG DISTANCE FROM SE CORNER AS MEAS. BY E.P. WATERMAN
SEC. 33, AS RECORDED BY DON RATEKIN, SET ON TOWN LINE
RR SPIKE WITH "X" CUT IN IT
SPIKE IS IN C/L E & W ROAD
SPIKE IS 5' WEST OF C/L OF ROAD TO SOUTH
P POLE S50E 73.51' TO NAIL 9' HIGH
P POLE N40W 57.69' TO NAIL 8' HIGH
P POLE N55E 81.36' TO NAIL 8' HIGH
8. W.Q. SMITH SURVEY REC. IN L 845, PG. 539-40 DATE 2-20-74
SAME INFO AS NO. 3 ABOVE
9. D. RATEKIN SURVEY REC. IN L. 899, PG. 321 DATE 4-15-76
SAME INFO AS NO. 3 ABOVE
10. JOHN CLAPP SURVEY REC IN L. 1015, PG 714
SAME INFO AS NO. 7 ABOVE
8. K. VAN ORDER SURVEY RECORDED IN L. 1057, PG. 718 DATED 10-31-83
SAME AS IN NO. 7 ABOVE
9. K.VAN ORDER SURVEY, DATED 6-19-85
SAME INFO AS NO. 7 ABOVE
10. MITCHELL SURVEYS WITNESS SHEET 1905
SAME INFO AS NO. 8 & 9 ABOVE
11. HOLLAND ENGINEERING WITNESS SHEET
SAME INFO AS NO. 8 & 9 ABOVE