

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

LIBER0006 PAGE353

For corners in <u>Allegan</u> <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T2N R15W	G-13
	T R	Clyde Twp.
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Donald R. Pitts, Jr. \_\_\_\_\_, in a field survey on October 1, 1998  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

1831 Calvin Britain Set post Pine 30 N 70 W 83 W Oak 10 N 8.5 E 64	1972 D. A. Ratekin - Survey L811, P592 Does not state monumentation Same witnesses as County Surveyors records	1993 Gary Bilow - L.C.R.C. L4, P200 Found 1.5" pipe N 57 E 10.8' 15" Oak N 79 E 42.3' 21" Oak S 29 E 65.2' 12" Cherry E 67' centerline North-South road W 20.9' Oak cluster E 105.60' NE corner Sec. 4, T1N, R15W
1969 County Surveyors Records 1.5" pipe 8" Oak N 80 E 10.8' 18" Oak E 42.3' 8" Cherry S 35 E 65.2' Centerline road E 67' Oak cluster W 21.3'	1972 D. A. Ratekin, L.C.R.C. L1, P370 1.5" pipe Same witnesses as County Surveyors records	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1 1/2" pipe  
Face 15" Oak N 57 E 10.5'  
Face 21" Oak N 79 E 42.1'  
Face 12" Cherry S 29 E 65.2'  
Centerline North-South road East 69'  
Face Oak cluster West 20.9'  
NE Corner Sec. 4, T1N, R15W, East 105.63  
Pulled 1 1/2" pipe and set standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520.  
Approved by Allegan County Remonumentation Peer Group November 10, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER

P.A. 345 OF 1990  
ALLEGAN COUNTY

DATE APPROVED NOV. 10, 1998  
COUNTY REP. [Signature]

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520  
G-1, T1N, R15W, Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520 East 105.63  
Nail with Allegan County Remonumentation tag S side 8" Quad Oak S 82 W 22.25'  
Nail with Allegan County Remonumentation tag NW side 15" Oak N 49 E 10.78'  
Nail with Allegan County Remonumentation tag N side 24" Oak N 74 E 43.18'  
Nail with Allegan County Remonumentation tag W side 12" Triple Cherry S 34 E 65.47'



Signed by Donald R. Pitts, Jr. Date December 29, 1998  
Surveyor's Michigan License No. 25867