

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

18800006 PAGE 354

For corners in <u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T2N R15W	H-13
	T R	
	T R	Clyde Twp.
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald R. Pitts, Jr. _____, in a field survey on October 1, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1831
Calvin Britain
Set post
Pine 6 N 79 W 18
Pine 7 N 16 E 62

1872
County Surveyors Records
N & S 1/4 posts found from old witnesses
New witness - Pine 14 N 47 1/2 W 41

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No corner found
Found railroad tie fence post with old wire fence running North

Set Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520 on line I-13, Town 2 North, Range 15 West through H-1, Town 1 North, Range 15 West in old wire fence running North. Approved by the Allegan County Remonumentation Peer Group December 8, 1998 and is accepted as a careful and faithful Perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 8, 1998
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520
H-1, Town 1 North, Range 15 West, Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520
East 64.00
Nail with Allegan County Remonumentation tag W side railroad tie fence post S 01 W 8.02'
Nail with Allegan County Remonumentation tag NW side 24" Twin Oak S 42 W 41.70'
Nail with Allegan County Remonumentation tag N side 12" Oak S 88 W 54.93'
Nail with Allegan County Remonumentation tag N side 24" Pine N 73 E 56.80'



Signed by [Signature] Date December 29, 1998
Surveyor's Michigan License No. 25867