

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

LIBR00006 PAGE 356

For corners in <u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T2N__R15W__ T____R____ T____R____ T____R____	J-13 Clyde Twp.
2. Property Controlling in Section	S____T____R____ S____T____R____	_____
3. Miscellaneous Property in Sec.	S____T____R____ S____T____R____	_____

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald R. Pitts, Jr., in a field survey on October 1, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831
Calvin Britain
Set post
Hemlock 6 N 53 E 37
Beech 12 N 76 W 17

1905 County Surveyors Records
I-13, Town 2 North, Range 15 West, West 2643.25'
K-13, Town 2 North, Range 15 West, East 2643.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner found
I-13, Town 2 North, Range 15 West to K-13, Town 2 North, Range 15 West, East 5287.06' (2643.53')
Set standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520
Equidistant and on line I-13, Town 2 North, Range 15 West to K-13, Town 2 North, Range 15 West
Approved by the Allegan County Remonumentation Peer Group, November 10, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED NOV. 10, 1998
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520
J-1, T1N, R15W, Standard Allegan County Remonumentation iron with red cap #23520 East 44.14'
Nail with Allegan County Remonumentation tag NW side 12" Twin Oak N 34 E 71.18
Nail with Allegan County Remonumentation tag W side 10" Maple S 43 E 50.11'
Nail with Allegan County Remonumentation tag NW side 6" Pine N 35 W 39.23'



Signed by [Signature] Date December 29, 1998
Surveyor's Michigan License No. 25867