

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98 JAN 21 PM 1:20
REGISTER OF DEEDS
ALLEGAN COUNTY
FILED

For Corners in ALLEGAN COUNTY	Located In:	Comer Code #
1. Public Land Survey SEC COR COMMON TO SEC. 1 & 2 CLYDE TWP.	T..2N R..15W T..... R..... T..... R..... T..... R.....	...K-1.....
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, RAYMOND MOORED, in a field survey on SEPTEMBER 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 9-9-97
COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND 1/2" IRON IN MON BOX WEST OF K-13 PER #4 ABOVE. MEASURED JOG AT 40.37' (MITCHELL 40.26') CORNER IS 0.11' NORTH OF TOWNSHIP LINE. SET 3/4" X 24" ALLEGAN COUNTY REMON IRON W/REMON CAP ON TOWNSHIP LINE AT MEASURED DISTANCE FROM K-13.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON 9-9-97

TOTAL LINEAL FEET OF ON ROAD TRAVERSING= 2665.48'
C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX.

- NAIL & TAG IN W SIDE 10" OAK SSE 37.50'
- NAIL & TAG IN W SIDE 10" TWIN OAK N15W 37.60'
- NAIL & TAG IN NW SIDE 10" OAK N30E 40.95'
- C/L ROAD NORTH 3' +/-
- SE CORNER SEC. 35 MANLIUS (K-13) EAST 40.37'

Signed by Raymond Moored Date 12/17/97
Surveyor's Michigan License No. 26463



GOVERNMENT CORNER HISTORY

SECTION CORNER COMMON TO SECTIONS 1 & 2
TOWN 2 NORTH, RANGE 15 WEST

K-1

- PART A: 1. G.L.O., L. LYON, D.S., 1831 NORTH BETWEEN SEC'S 1 & 2
84.13 INTERSECT N. BOUNDARY 61 LKS W OF
POST WHERE SET POST COR SECTIONS 1 & 2
PINE 13 N27 W 22
DOGWOOD 4 S54 E 18
2. CO SURVEYOR RECORDS H. MACDOUGAL JUNE 15 & 16 1906
SURVEY OF SEC 2
FD STONE AT NE CORNER
DIST S TO E 1/4 COR 3,008'
(GLO = 2912.56)
3. D. RATEKIN SURVEY REC IN L 826, PG 666 DATE JANURAY 26, 1973
USED COR - NO WITS
DIST TO K-13 40.26' E
4. MITCHELL SURVEYS WITNESS SHEET 1980
10" OAK S SW 37.5'
10" TWIN OAK N NW 37.6'
MON BOX E 40.26'