

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

LIBR0006 PAGE 357

For corners in
Allegan
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T2N ___ R15W ___ K-13
T ___ R ___ Clyde Twp.
T ___ R ___
T ___ R ___

2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH
Register of Deeds Stamp & File Number

I, Donald R. Pitts, Jr., _____, in a field survey on October 1, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1831 1905 County Surveyors Records
Calvin Britain J-13, T2N, R15W, West 2643.25'
Set post
Pine 30 N 40 E 24
Pine 12 N 35 W 20

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED Nov. 10, 1998
COUNTY REP. [Signature]

1991
Gary Bilow - L.C.R.C. 14, P119
Found 2"x6" rectangular iron mass
Set concrete monument and MDNR cap
N 89 E 26.32 1/2" rebar at NW corner of Sec. 1, T1N, R15W
S 52 E 68.7 stop sign post
N 18 W 37.58 set nail and MDNR tag in W face 12" Oak
N 42 E 42.20 set nail & MDNR tag in 20" Oak
E 33' centerline of gravel surface 50th St. S 7' centerline of 112th Ave.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found concrete monument with MDNR cap
1/2" rebar at NW corner Sec. 1, T1N, R15W, N 89 E 26.25'
Stop sign post S 50 E 67.9'
Nail and MDNR tag in W face 12" Oak N 18W 37.55'
Nail and MDNR tag in 20" Oak N 42 E 42.15'
Centerline 50th Street East 33'
Centerline 112th Avenue North 7'
Pulled concrete monument with MDNR cap and set standard Allegan county Remonumentation 3/4"x24" iron with Red cap #23520.
Approved by the Allegan County Remonumentation Peer Group November 10, 1998 and is accepted as a careful and Faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520.
K-1, T1N, R15W, Standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520 East 26.25'
Nail with Allegan County Remonumentation tag SE side 10" Oak N 53 E 73.33'
Nail with Allegan County Remonumentation tag NE side 8" Oak S 56 E 92.80'
Nail with Allegan County Remonumentation tag SE side 12" Pine S 46 W 52.44'
Nail with Allegan County Remonumentation tag W side 12" Oak N 02 E 58.83'



Signed by Donald R. Pitts, Jr.
Surveyor's Michigan License No. 25867

Date December 29, 1998