

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98 JAN 21 PM 1:20
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
FILED

For Corners in ALLEGAN COUNTY	Located In:	Corner Code #
1. Public Land Survey NORTH 1/4 COR SEC. 1 CLYDE TWP.	T..2N R..15W T..... R..... T..... R..... T..... R.....	...L-1.....
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, RAYMOND MOORED, in a field survey on SEPTEMBER 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
SEE BACK OF SHEET FOR CORNER HISTORY


APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 10-14-97
COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1" IRON BAR 20.18' WEST OF L-13 PER #4 ABOVE. MEASURED 20.21' TO L-13 PER #4 AS PREVIOUSLY ESTABLISHED. CORNER AS FOUND WAS SET ON LINE AT JOG DISTANCE FROM L-13 AND ON LINE TO AN ERRONEOUS CORNER AT M-13 (TWP. COR.). RESET CORNER ON LINE BETWEEN CORRECTED L-13 AND K-13 ON TOWNSHIP LINE AT JOG DISTANCE FROM L-13.

ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON 10-14-97

TOTAL LINEAL FEET OF ON ROAD TRAVERSING= 2647.44'
C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
-NAIL & TAG IN W SIDE 13" OAK S15E 81.60'
-WEST EDGE CONC. R/W MARKER S45W 50.60'
-FACE OF CONC R/W MARKER N40E 95.30'
-3/4" REMON IRON W/ CAP (L-13 MANLIUS) EAST 20.21'.
-C/L STATE HIGHWAY M-89 NORTH 17.5'
-C/L 49TH STREET TO NORTH IS WEST 18' +/-



Signed by Raymond Moored Date 12/17/97
Surveyor's Michigan License No. 26463

GOVERNMENT CORNER HISTORY

NORTH 1/4 CORNER SECTION 1
TOWN 2 NORTH, RANGE 15 WEST

L-1

PART A: 1. CORNER NOT SET BY G.L.O.

2. DON RATEKIN WITNESS CARD FOR SEC 36
MANLIUS SHOWS JOG DIST FROM L-1 TO L-13 OF
20.15'
NO WITNESSES

3. M.D.O.T. R/W MAP FOR HWY M-89
1/4 COR 7.04' S OF C/L RD

4. M.C.N.R. SURVEY OF SEC 36, T3N, R15W (Below)
FD 1" BAR 20.18' W OF L-13

NO OTHER HISTORICAL DATA AVAILABLE