

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 0006 PAGE 358

For corners in <u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T2N R15W	L-13
	T R	Clyde Twp.
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald R. Pitts, Jr., in a field survey on October 1, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831 1991
Calvin Britain Gary Bilow- L.C.R.C. L4, P119
Set post Set concrete monument with MDNR cap
Pine 7 N 5 W 36 Equidistant and on a straight line between M-13 and K-13
Pine 7 N 75 E 41 S 50 E 6.12 found capped rebar previously recorded as the N 1/4 cor. of Sec. 1, T1N, R15W (L.C.R.C. L3, P364)
E 13.16 concrete monument with MDNR cap at N 1/4 corner Sec. 1, T1N, R15W
N 10 W 47.25' set nail and MDNR tag in W face 24" White Pine
N 34 W 66.63' set nail and MDNR tag in E face 27" Oak
N 70 E 71.78' set nail and MDNR tag in N face 33" Oak


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument (no cap)
Capped iron rebar previously recorded as N 1/4 corner Sec. 1, T1N, R15W, (LCRC-Liber 3, Page 364) S 50 E 6.12'.
Concrete monument with MDNR cap at N 1/4, Sec. 1, T1N, R15W, East 13.11'
Nail and MDNR tag in W face 24" White Pine N 10 W 47.44'
Nail and MDNR tag in E face 27" Oak N 34 W 66.63'
Nail and MDNR tag in N face 33" Oak N 70 W 77.75'
Pulled concrete monument and set standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520.
Approved by Allegan County Remonumentation Peer Group November 10, 1998 and is accepted as a careful and Faithful perpetuation of the position of the original corner.
Also pulled iron rebar recorded in L.C.R.C. - Liber 3, Page 364

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED Nov 10, 1998
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520
L-1, T1N, R15W, standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520 East 13.11'
Nail with Allegan County Remonumentation tag NW side 12" Twin Pine N 46 E 54.03'
Nail with Allegan County Remonumentation tag NE side 24" Oak S 45 E 71.91'
Nail with Allegan County Remonumentation tag NW side 24" Sassafras S 19 W 61.11'
Nail with Allegan County Remonumentation tag NE side 30" Oak N 39 W 66.55'



Signed by Donald R. Pitts, Jr. Date December 29, 1998
Surveyor's Michigan License No. 25867