

MAR 07 2000

FILED

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T. 2N R. 15W	M-11
N.E. COR., SEC. 36	T..... R.....
S.E. COR., SEC. 25	T..... R.....
T.2N., R.15W.	T..... R.....
CLYDE TWP.	T..... R.....
2. Property Controlling in section	S.....T.....R.....
	S.....T.....R.....
3. Miscellaneous Property in Sec.	S.....T.....R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

00 FEB -1 AM 8:38

Joyce A. [Signature]
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A. of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831 L. LYON
SET POST
W. OAK 8 S28W 24
PINE 28 N32W 53

NO OTHER CORNER HISTORY AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" IRON BAR IN C/L GRAVEL ROAD AND EXISTING M.D.N.R. WITNESS TABS IN SURROUNDING TREES, M.D.N.R. CONFIRMED THEY FOUND CORNER AND TOOK WITNESSES BUT DID NOT ACTUALLY USE CORNER FOR ANY SURVEY. REMOVED FOUND CORNER AND SET STANDARD ALLEGAN COUNTY REMON IRON WITH CAP.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON DEC. 14, 1999

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED DEC. 14, 1999
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP

-30" OAK DNR TAB NNE SIDE	S30°E	50.02'
-28" OAK DNR TAB SW SIDE	S16°E	87.13'
-36" OAK DNR TAB NW SIDE	S26°W	50.99'
-10" TW OAK DNR TAB NE SIDE	N52°W	24.89'
-A-11, T.2N., R.14W.	SOUTH	31.11'

Raymond Moored

Date 12/24/99

Surveyors License No. 26463

