

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|---|---------------|--------------------|
| 1. PUBLIC LAND SURVEY <u>13</u> T. <u>2</u> N. <u>15</u> W. | | M-5 |
| 2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. S., R. _____ E. W. | | |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W. | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

M-5 Oak Stake
 Oak 8" SW 35.5'
 Oak 8" SE 62'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-5 Measure N. from N.W. Corner 18
 T2N, R14W Dug and found remains
 of old wooden stake, Set concrete
 monument.
 4" x 36" with aluminum cap

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 4" x 36" Concrete monument with aluminum cap.
 S. 75° W. 72.54' 20" B. Oak
 N. 44° W. 49.97' 20" R. Oak
 N. 52° E. 28.49' 6" W. Oak
 S. 50° E. 29.71' 8" W. Oak
 South 138.15' NW Corner 18
 T2N R14W

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 12-1-82
CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

