

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
 (County)

Located In: Corner Code #/

1. Public Land Survey	T 2N R 15W	E12
	T 2N R 15W	F11
	T R	
	T R	
2. Property Controlling in Section	S 33 T 2N R 15W	3
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

F11 January 19, 1993
 3 January 20, 1993

I, **Gary C. Bilow**, in a field survey on **E12 January 20, 1993**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E12: Post established by U.S. Deputy Surveyor C. Britain in 1831 - accessories: W. Oak 12 N60W 8 links and W. Oak 9 S60E 30 links. Undated Allegan County Surveyor records obtained from Wightman-Moored reference a Stone - no accessories. Corner recorded under Act 74, PA 1970 by D. Ratekin (PS #8781) in Liber 2, Page 207 as "Found Iron - accessories: SE cor Store N55W 53.30', SW cor House N60E 55.60', NW cor Tele outlet S40E 47.50', Centerline road West 1.0'".

F11: Post established by U.S. Deputy Surveyor C. Britain in 1831 - accessories: Beech 12 S28E 31 links and Beech 7 N52W 16 links. Undated records obtained from Wightman-Moored show distance ties to this corner and nothing else. Allegan County Surveyor D. Allen on a 1958 survey work sheet of the Northwest 1/4 of Section 33 shows the same distance ties to this corner as the undated records and nothing else.

3: Allegan County Surveyor D. Allen in 1958 shows this location on a survey work sheet of the Northwest 1/4 of the Section but does not show if anything was set. This record obtained from Wightman-Moored.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E12: Found 3/4" Iron bar in Monument box and three (3) of Ratekin's witnesses. Accepted this corner as the best evidence of the original GLO post.

F11: Established corner midway on line between corners E11 and G11.

3: Found 1" Iron bar in Monument box almost midway (+/- 0.07') on line between corners E11 and E12. Accepted this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E12: Found 3/4" Iron bar in Monument box
 N61E 55.60', SW corner of House
 S34E 47.50', NW corner Telephone outlet
 S40W 56.16', Nail & Tag in Power pole
 West 1.0', Centerline North-South road
 N55W 53.30', SE cor building

F11: Set 1/2" x 36" rebar encased in 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet
 N89E 10.85', Nail & Tag in 7" Oak
 S33E 7.20', Nail & Tag in 5" Oak
 S68W 9.74', Nail & Tag in 3" Oak
 N41W 14.78', Nail & Tag in twin 2" Oak

3: Found 1" Iron bar in Monument box
 N40W 49.59', Nail & Tag in Power pole
 N16W 102.70', Nail & Tag in Power pole
 N43E 57.80', Nail & Tag in 13" Oak
 S45E 45.5', Telephone Box
 East 2.81', Centerline North-South road

Signed by Gary C. Bilow
 Surveyor's Michigan License No. 26453

Date 3/5/93



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN-28, 1971 REVISED MAY 14, 1975 REPEALED JAN. 1983