

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan (County)	Located In:	Corner Code #/1
1. Public Land Survey	T 2N R 15W	F13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S 33 T 2N R 15W	Prop
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Pro January 25, 1993

I, Gary C. Bilow, in a field survey on F13 January 19, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

F13: Post established by U.S. Deputy Surveyor C. Britain in 1831 - accessories: Aspen 6 N71E 25 links and W. Oak 14 N84W 22 links. Undated records obtained from Wightman-Moored show "Stone - accessories: Oak 10 SW 57.5' and Oak 10 SE 36'". Corner recorded under Act 74, PA 1970 by D. Ratekin (PS #8781) as "Found iron (wellpoint with 3" x 6" steel plate on top) - accessories: 7" Oak SSW 5.15', 15" twin Oak SW 56.4', 10" Cherry E 93.5', 3" Pine ENE 65.7', 6" triple Oak NNW 57.4'".

Prop: Allegan County Surveyor D. Allen in 1958 shows this location on a survey work sheet of the Northwest 1/4 of the Section but does not show if anything was set. This record obtained from Wightman-Moored.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F13: Found Wellpoint with 3" x 6" steel plate on top and two (2) of Ratekin's witnesses. Accepted this corner as the best evidence of the original GLO post.

Prop: Established corner midway on line between corners #4 (calculated intersection of 1/16th lines) and #5 (recorded this date).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F13: Wellpoint with 3" x 6" steel plate on top
 S25W 5.61', Nail & Tag in 11" Oak
 S57W 57.25', Nail & Tag in twin 19" Oak
 N42W 21.21', Nail & Tag in 10" Oak
 South 11', Centerline East-West trail
 East 122.71', N 1/4 cor Sec-4 T1N R15W



Prop: Set 1/2" x 36" rebar encased in 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet
 N67E 1.41', Nail & Tag in Fence post
 S7W 9.06', Nail & Tag in 3" Oak
 N40W 25.85', Nail & Tag in 16" Pine
 N6W 19.05', Nail & Tag in 16" Pine
 N59E 2.48', Bedrail

Signed by Gary C. Bilow Date 3/5/93
 Surveyor's Michigan License No. 26453