

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Allegan  
(County)

	Located In:	Corner Code --//
1. Public Land Survey	T 2N R 15W	G13
	T 2N R 15W	G12
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gary C. Bilow, in a field survey on January 22, 1993, 19\_\_\_\_ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G13: Post established by U.S. Deputy Surveyor C. Britain in 1831 - accessories: Pine 30 N70W 83 links and W. Oak 10 N8-1/2E 64 links. Undated Allegan County Surveyor records obtained from Wightman-Moored reference a Stake - no accessories. Records dated 1969 obtained from Wightman-Moored specify "1-1/2" Pipe - accessories: 8" Oak ENE 10.8', 18" Oak East 42.3', 8" Cherry SSR 65.2', C1 road East 67', Oak cluster West 21.3'. Corner recorded under Act 74, PA 1970 by D. Ratekin (PS #8781) in Liber 1, Page 370 as Found 1-1/2" Pipe with same accessories as stated above.

G12: Post established by U.S. Deputy Surveyor C. Britain in 1831 - accessories: W. Oak 30 N31E 51 links and W. Oak 12 S70W 30 links. Undated records from Wightman-Moored show a "Stake - accessories: W. Oak 12 SE 17.5', W. Oak 12 NW 31.7', W. Oak 8 NW 28". Corner recorded under Act 74, PA 1970 by D. Ratekin (PS #8781) in Liber 1 Page 370 as "Found 3/4" pinch pipe - accessories: 16" R. Oak S50E 17.8', 15" B. Oak N25E 60.9'. St. sign N35W 22.05', 15" W. Oak N65W 31.3', 12" W. Oak S55W 54.9".

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G13: Found 1-1/2" Pipe and all of Ratekin's witnesses. Accepted corner as the best evidence of the original GLO post.

G12: Found 3/4" pinch pipe and four (4) of Ratekin's witnesses. Accepted this corner as the best evidence of the original GLO post.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G13: Found 1-1/2" Pipe	G12: Found 3/4" pinch pipe
N57E 10.8', 15" Oak	S50E 17.8', 16" R. Oak stump
N79E 42.3', 21" Oak	N30E 60.9', 14" B. Oak
S29E 65.2', 12" Cherry	N15W 22.05', Street sign
East 67', Centerline North-South road	N50W 31.3', 18" W. Oak
West 20.9', Oak Cluster	S40W 64.71', Nail in 12" Oak
East 105.60', NE cor Sec-4 TIN R15W	



Signed by Gary C. Bilow Date 3/5/93  
 Surveyor's Michigan License No. 26453

PAGE 182 PAGE 182