

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Allegan (County)	Located In:	Corner Code -//
1. Public Land Survey	T 2N R 15W	F12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 33 T 2N R 15W	8
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Gary C. Bilow, in a field survey on January 22, 1993, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	●	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

F12: Post not established by U.S. Government Survey. Old Allegan County Survey records call for a Oak stake - no accessories (not dated). Other undated Allegan County Surveyor Records indicate a "Stake & Crockery - accessories: 15" W. Oak WSW 58.9', St. Sign NNE 30', 12" B. Oak SW 39.4', 6" B. Oak SSE 60". Records obtained from Wightman-Moored (dated 1973) state "Found 5/8" Iron - accessories: Street sign N20E 29.90', 10" Pine S20E 59.9', 16" B. Oak S15W 42.70', 18" B. Oak S50W 39.07', 18" W. Oak S75W 58.8', Centerline road 5' North". Corner recorded under Act 132, PA 1970 in Liber 973, Page 489 by J. Dillingham (PS #16927) as "Found Iron and lists all of Wightman-Moored's accessories.

8: Allegan County Surveyor D. Allen in 1958 performed a survey of the Northwest 1/4 of Section 33 but does not show setting anything. Undated records obtained from Wightman-Moored show "Iron - accessories: 18" Pine SE 83.0', 21" twin Oak NE 34.6', P. pole NW 31.7', 18" B. Oak NW 44.4'".

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

F12: Found 1" Iron bar and two (2) of Dillingham's accessories. Accepted this corner.

8: Found 1-1/8" Iron pipe on the East-West 1/4 line and 0.25' East of the midpoint between corners E12 and F12 and one (1) witness. Accepted this corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

F12: Found 1" Iron bar  
 S15W 42.70', 16" B. Oak Stump  
 North 3', Centerline East-West road  
 S42W 55.74', Nail & Tag in 10" twin Oak  
 S70W 92.50', Nail & Tag in Power pole  
 North 33.00', MDNR monument  
 S18E 60.12', 17" Pine



8: Found 1-1/8" Iron pipe and raised with 1/2" x 24" capped rebar  
 N22W 37.66', Nail & Tag in Power pole  
 N27E 45.00', Nail & Tag in 20" Oak  
 S58E 83.70', Nail & Tag in 25" Pine  
 North 33.00', MDNR monument

Signed by Gary C. Bilow Date 3/5/93  
 Surveyor's Michigan License No. 26453