

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN

(County)	Located In:	Corner Code ##
1. Public Land Survey	T 2N R 12W	J-5
	T 2N R 12W	K-5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, GARY C. BILOW, In a field survey on SEPTEMBER 12, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J-5) OLD RECORDS OF DONALD A. RATEKIN, RLS #8781, AT OFFICES OF WIGHTMAN-MOORED INC., IN ALLEGAN SHOW: "N1/4 POST - IRON, 24" BEECH STUMP NNE 22.2', 10" OAK NW 20.1', 16" OAK SSE 23.6', 22" BEECH STUMP NE 32.3', 6' EAST OF FENCE NORTH, 3' NORTH OF CENTERLINE OF ROAD". CORNER SHOWN ON RECORDED PLAT OF "DOEZEMA BIG LAKE PLAT" (RECORDED IN LIBER 11 OF PLATS, PAGES 94-95). FOUND NO RECORD OF CORNER IN ALLEGAN COUNTY SURVEYORS RECORD OR IN ACT 74, P.A. 1970 LAND CORNER RECORDATION CERTIFICATES.

(K-5) OLD RECORDS OF DONALD A. RATEKIN, RLS #8781, AT OFFICES OF WIGHTMAN-MOORED INC., IN ALLEGAN SHOW: "NE COR. SEC. 14 - STAKE, 22" WALNUT SSW 20.2', 20" WALNUT NE 26.8', FENCE POST NORTH 23.9', 18" WALNUT NORTH 25.8', 16" WALNUT NW 27.1'". FOUND NO RECORD OF CORNER IN ALLEGAN COUNTY SURVEYORS RECORD OR IN ACT 74, P.A. 1970 LAND CORNER RECORDATION CERTIFICATES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J-5) FOUND 1" DIAMETER IRON PIPE IN ACCORD WITH ABOVE NOTED ACCESSORIES AS FOLLOWS: 10" (NOW 18") OAK, 16" (NOW 24") OAK, FENCE LINE NORTH, AND CENTERLINE OF GRAVEL ROAD. FOUND PIPE TO BE IN SUBSTANTIAL ACCORD WITH ORIGINAL MONUMENTATION OF "DOEZEMA BIG LAKE PLAT" RELATIVE TO THE DIMENSIONS APPEARING ON THE FACE OF THE PLAT.

(K-5) FOUND 5/8" IRON ROD IN ACCORD WITH THE STUMP REMAINS OF THE 22" WALNUT SSW, AND THE 16" WALNUT NW, AS NOTED ABOVE.

ACCEPTED BOTH MONUMENTS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER LOCATIONS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J-5) FOUND 1" IRON PIPE
 SW 26.20' SET NAIL AND MICHIGAN DEPARTMENT OF
 NATURAL RESOURCES TAG IN NW FACE 15" OAK
 NNW 20.38' SET NAIL AND MDNR TAG IN SW FACE 18" OAK
 NW 29.11' SET NAIL AND MDNR TAG IN NE FACE 13" OAK
 NNW 23.6' CENTER OF WOOD CORNER FENCE POST

(K-5) FOUND 5/8" IRON BAR
 S18W 121.50' SET PK NAIL AND MDNR TAG IN POWER POLE
 N02W 28.90' SET PK NAIL IN EAST FACE 18" WALNUT
 N62E 56.86' SET NAIL AND MDNR TAG IN SE FACE 18" WALNUT
 CORNER IS APPROXIMATELY 300' EAST OF A DRIVEWAY TO THE
 SOUTH AND IS FLUSH WITH THE GRAVEL SURFACE OF 120TH AVENUE.

Signed by Gary C. Bilow
 Surveyor's Michigan License No. 26453

Date 3/29/91

