

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>2</u> N. <del>S.</del> R. <u>15</u> E. <del>W.</del>		<u>I-3, I-4, I-5</u>
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. S. R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

AUG 12 9 42 AM 1974  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICH.  
 FILED  
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, F. E. Spicer do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 17, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

<u>I-3 -</u>	<u>I-4 -</u>	<u>I-5 -</u>
Cor fence NW 35.1'	None	Nail NW side 24" Oak S22°W 62.70'
14" Oak NNE 50.20'		Nail N side 12" W Ch N75°W 101.35'
St sign E 6.82'		Nail S side 12" Pine N55°E 75.96'
27" Pine NW 29.3'		Nail S side 40" Oak S75°E 78.21'
14" Apple SW 100.20'		In $\odot$ rds N-S & E-W (52nd St N-S & 120th Ave E-W)


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-3 - Found by above wlt and accepted as cor
- I-4 - Measured S from NW cor Sec 11 2652.0' - change in kind of trees on line E 5304.32' - Found iron @ intersection of rd E-W - Set "T" iron on line & halfway between NW & SW cors of sec as found
- I-5 - Found by above wlt and accepted as cor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>I-3 - 2" iron pipe</u>	<u>I-4 - "T" iron</u>	<u>I-5 - Solid iron rod</u>
Cor fence NW 35.1'	16" Pine S70°E 58.00'	Nail NW side 24" Oak S22°W 62.70'
14" Oak NNE 50.20'	8" Oak N50°W 40.29'	Nail N side 12" W Ch N75°W 101.35'
St sign E 6.82'	24" Oak N20°E 86.43'	Nail S side 12" Pine N55°E 75.96'
27" Pine NW 29.3'	10" Oak S15°E 82.80'	Nail S side 40" Oak S75°E 78.21'
14" Apple SW 100.20'		In $\odot$ rds N-S & E-W (52nd St N-S & 120th Ave E-W)

SIGNED BY F. E. Spicer DATE 8/2/74  
 F. E. Spicer  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 7877  
 FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 MICHIGAN REGISTERED LAND SURVEYOR



PAGE 120