

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN

| | | |
|------------------------------------|--------------------------|---------------|
| (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>2N</u> R <u>15W</u> | <u>H1</u> |
| | T <u>2N</u> R <u>15W</u> | <u>H2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, GARY C. BILOW, in a field survey on JANUARY 7, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

(H-1) CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. SHOWN IN COUNTY SURVEYOR RECORD BY E.P. WATERMAN (1887) AS "60V. STAKE" 1.79 CHAINS WEST OF THE SOUTH 1/4 CORNER OF SECTION 34, T3N-R15W. NO OTHER ACCESSORIES NOTED. FOUND NO RECORD OF CORNER IN MICHIGAN DEPT. OF TRANSPORTATION FIELD NOTES FOR STATE HIGHWAY M-89. CORNER RECORDED BY D.A. RATEKIN, 1972 (LCRC LIBER 2, PAGE 60) AS FOUND 3/4" IRON IN MONUMENT BOX. RATEKIN NOTES OLD MONUMENT AND ACCESSORIES: BOAT SPIKE; 8" OAK N19E 84.12', 9" TWIN OAK N17W 41.46', 10" TWIN OAK S62W 94.60'.

(H-2) CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. SHOWN IN COUNTY SURVEYOR RECORD BY E.P. WATERMAN (1887) AS "STAKE". NO ACCESSORIES NOTED. CORNER RECORDED BY D.A. RATEKIN IN 1977 (LCRC LIBER 3, PAGE 207) AS 1/2" IRON.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H-1) FOUND AND ACCEPTED 1/2" DIA. PIPE IN MONUMENT BOX AT CENTERLINE OF HWY. M-89 AND CENTERLINE OF ROAD TO THE SOUTH. OLD TIE SHOWN ON RATEKIN'S LCRC CHECKS TO 14" TWIN OAK NW. ACCESSORIES TO OAK TREES SHOWN ON PREVIOUSLY RECORDED SURVEY (LIBER 1057, PAGE 720) ALSO CHECK.

(H-2) FOUND AND ACCEPTED 3/8" IRON BAR IN MONUMENT BOX. RATEKIN'S TIE TO 20" OAK (NOW 24" OAK) CHECKS. DETERMINED THIS MONUMENT TO BE 1.07' WEST AND 1.51' SOUTH OF THE INTERSECTION OF STRAIGHT LINES CONNECTING OPPOSITE 1/4 CORNERS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H-1) FOUND 1/2" IRON PIPE IN MONUMENT BOX
 N20W 41.62' FD SPIKE EAST FACE 14" TWIN OAK
 N65E 73.84' SET NAIL AND MDNR TAG SE FACE 10" TRIPLE OAK
 S15W 91.37' SET NAIL AND MDNR TAG EAST FACE 17" OAK.

(H-2) FOUND 3/8" IRON BAR IN MONUMENT BOX
 N35W 87.09' FD PK NAIL WITH TAG SW FACE POWER POLE
 S20W 108.36' SET NAIL AND MDNR TAG EAST FACE 12" AND 17" TWIN OAK
 N80E 68.63' SET NAIL AND MDNR TAG SOUTH FACE 24" OAK.
 SOUTH, 15' CENTERLINE OF EAST-WEST GRAVEL ROAD.



Signed by Gary C. BiLow Date 3/8/91
 Surveyor's Michigan License No. 26453