

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
ALLEGAN

(County)

Located In:

Corner Code ##

1. Public Land Survey	T	<u>2N</u>	R	<u>15W</u>	<u>6-3</u>
	T	<u>2N</u>	R	<u>15W</u>	<u>6-2</u>
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GARY C. BILOW, in a field survey on JANUARY 7, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(G-3) CORNER POST ESTABLISHED BY U.S. GOVERNMENT DEPUTY SURVEYOR C. BRITAIN, 1831. ACCESSORIES: PINE 14 N84E 22, W. ASH 14 S43W 39. ORIGINAL CORNER RECOVERED SEPT. 1887 BY ALLEGAN COUNTY SURVEYOR E.P. WATERMAN. NO ADDITIONAL ACCESSORIES NOTED. CORNER RECORDED UNDER ACT 74, P.A. 1970 BY D.A. RATEKIN IN 1972 (L.C.R.C. RECORDED LIBER 1, PAGE 245) AS FOUND SOLID BAR. RATEKIN'S ACCESSORIES: PK NAIL SE ROOT 18" PINE N45W 67.57', PK NAIL P. POLE S40W 66.80', ST. SIGN S45E 34.85'.

(G-2) CORNER POST ESTABLISHED BY U.S. GOVERNMENT DEPUTY SURVEYOR C. BRITAIN, 1831. ACCESSORIES: W. OAK 16 S85E 51, DD 12 N75W 24. COUNTY SURVEYORS RECORD SHOWS STAKE AND BRICK (E.P. WATERMAN, 1887). CORNER RECORDED BY D.A. RATEKIN IN 1972 (L.C.R.C. RECORDED LIBER 1, PAGE 245) AS FND. 1/2" REF. ROD. RATEKIN'S ACCESSORIES ARE AS FOLLOWS: ST SIGN W 20.7', NAIL IN S. ROOT 16" OAK S55E 44.39' 9" PINE S85W 36.7'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(G-3) FOUND AND ACCEPTED 1/2" IRON BAR WITH PLASTIC CAP #16042 IN MONUMENT BOX AT APPROXIMATE CENTERLINE INTERSECTION OF ROADS N-S-E-W. RATEKIN'S RECORDED ACCESSORIES TO PINE AND P. POLE CHECK.

(G-2) FOUND AND ACCEPTED 1/2" IRON BAR. RATEKIN'S RECORDED TIE TO PINE CHECKS TO 14" WHITE PINE.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(G-3) FOUND 1/2" IRON BAR WITH CAP #16042 IN MONUMENT BOX  
 N50W 68.65' SET NAIL AND MICHIGAN DEPT. OF NATURAL RESOURCES TAG IN SW'LY FACE 20" W. PINE  
 S25W 67.10' SET NAIL AND MDNR TAG E. FACE POWER POLE  
 S45E 91.56' SET NAIL AND MDNR TAG SW'LY FACE POWER POLE

(G-2) FOUND 1/2" IRON BAR  
 S55E 47.77' SET NAIL AND MDNR TAG IN 11" W. PINE.  
 S85W 37.30' SET NAIL AND MDNR TAG S. FACE 14" W. PINE  
 S25W 113.81' SET NAIL AND MDNR TAG E. FACE POWER POLE  
 EAST 1' CENTERLINE OF BITUMINOUS PAVEMENT



Signed by Gary C. Bilow  
 Surveyor's Michigan License No. 26453

Date 3/8/91