

SURVEY & REMONUMENTATION

ALLEGAN COUNTY REMONUMENTATION

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
Allegan

	Located In:	Corner Code #
	Ganges Township	
1. Public Land Survey	T <u>2</u> NR <u>16</u> W	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1994 DEC 16 AM 9:54
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN
George J. Mitchell
FILED
Register of Deeds Stamp & File Number

I, George J. Mitchell in a field survey on November 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	8	7	6	5	4	3	2	1				
7												
8	9	8	7	6	5	4	3	2	1			
9												
10	10	9	8	7	6	5	4	3	2	1		
11												
12	11	10	9	8	7	6	5	4	3	2	1	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
B-13
L. LYON SET POST 1831 OLD NOTES OF H. MC DOUGALL
7" BEECH N70W 41 LKS. "STAKE AND STONES AROUND IT"
7" IRONWOOD N71E 32 LKS.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 10-11-94
COUNTY REP. *Rich L. Van Orden*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
B-13
NO EVIDENCE OF CORNER WAS FOUND. SET CORNER ON INTERSECTION OF TOWNSHIP LINE AND A LINE PRODUCES SOUTH FROM NORTH QUARTER POST THRU THE CENTER OF THE SECTION AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
MEASURED 3511.25 FEET (PLATTED AS 3511.34 FEET) TO EAST MONUMENT IN MAE'S SLYVAN SHORES PLAT. MEASURED 2628.70 FEET EAST TO C-13 & 2613.29 FEET NORTH TO RECORD CENTER OF SECTION 31, TOWN 2 NORTH, RANGE 16 WEST.



C. Description of monument for corner and accessories established to perpetuate locating the position of corner:
B-13
SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.
A.C. remon tag & nail in East side of 6" Ash AZ. 170° 6.40'
A.C. remon tag & nail in South side of 20" Maple AZ. 85° 28.54'
A.C. remon tag & nail in West side of 14" Ash AZ. 05° 8.62'
A.C. remon tag & nail in SW side of 12" Ash AZ. 285° 11.27'
Casco Township Corner B-1 AZ. 90° 93.70'

Signed by George J. Mitchell Date NOVEMBER 4, 1994
Surveyor's Michigan License No. 19618

LIBER 0005 PAGE 019