

# SURVEY & REMONUMENTATION

APR 25 1995

## ALLEGAN COUNTY REMONUMENTATION

**COMMISSION**  
for corners in  
Allegan

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

	Located in:	Corner Code #
	Ganges Township	
1. Public Land Survey	T <u>2</u> N R <u>16</u> W	C-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1994 DEC 16 AM 9:56  
 Register of Deeds  
 ALLEGAN COUNTY MICHIGAN  
*James A. Collette*

FILED

Register of Deeds Stamp & File Number

I, George J. Mitchell in a field survey on November 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessones and/or subsequent restoration:

C-13

SEE BACK OF SHEET

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 10-11-94  
 COUNTY REP. *Rich A. Van Dyke*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13

FOUND FENCE POST FLUSH WITH GROUND AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

20" Cherry South 47' to center  
Casco Township corner East 90.81'

MEASURED 2634.34 FEET EAST TO D-13 & 2628.70 FEET WEST TO B-13



C. Description of monument for corner and accessones established to perpetuate locating the position of the corner:

C-13

REPLACED POST WITH 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP.

A.C. remon tag & nail in West side of Tele. Pole	AZ. 90°	9.94'
A.C. remon tag & nail in West side of 6" Maple	AZ. 20°	30.90'
A.C. remon tag & nail in South side of 6" Ash	AZ. 270°	54.21'
A.C. remon tag & nail in West side of 8" ash	AZ. 180°	46.01'
Casco Township Corner C-1	AZ. 90°	90.81'

Signed by *George J. Mitchell* Date November 4, 1994  
 Surveyor's Michigan License No. 19618

LIBER 0005 PAGE 067

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

SEE BACK OF SHEET FOR SHEET 2

*Allegan*

C-13 T2N, R16W  
SW CORNER SECTION 32  
GANGES TOWNSHIP

1831 S. SYRN

SET POST @ 80.00 Ch.  
10" BEECH N61W 42 Lks  
9" BEECH N71 1/2E 32 Lks

MDOT 1969

STEEL FENCE POST  
FLUSH WITH GROUND  
21" MAPLE - N20E - 71.05  
18" MAPLE - N75E - 31.08  
16" CHERRY - S05W - 47.11  
NW COR. SEC.5, CASCO-EAST - 90.84

RATEKIN CARDS (NO DATE) SAME AS ABOVE

HOLLAND ENGINEERING (NO DATE) SAME AS ABOVE

DON RATEKIN 7/29/71 L.C.R.C. L.1, P.79  
REASON FOR... SAME AS ABOVE

MITCHELL 1994 FOUND FENCE POST FLUSH WITH GROUND  
20" CHERRY SOUTH 47' TO CENTER  
CASCO CORNER EAST 90.81'