

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
ALLEGAN COUNTY..... Located in: ..GANGES..... Township  
Corner Code #

1. Public Land Survey T.2 N., R.16 W. ....D-1.....  
T..... R..... N1/4 POST SEC. 5
2. Property Controlling S..... T..... R.....  
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....  
Property in Sec. S..... T..... R.....
4. Lot No. ...., Recorded Plat .....
5. Private Claims.....

REGISTER OF DEEDS  
ALLEGAN COUNTY

97 JAN 22 11:23

E I I E N

Register of Deeds Stamp & File Number

I, .... George J. Mitchell....., in a filed survey on ...October 29, 1996..... do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
D-1  
NOT SET BY GLO

SEE SHEET 2 OF 2 FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 11-12-96  
COUNTY REP. [Signature]



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
D-1

FOUND BOAT SPIKE IN MONUMENT BOX FROM CORNER HISTORY AND ACCEPTED ITS LOCATION. THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER. THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMBER 12, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
D-1

REPLACED BOAT SPIKE WITH ALLEGAN COUNTY STANDARD 3/4" BY 36" IRON PIN WITH REMON CAP IN EXISTING MONUMENT BOX.

A.C. REMON TAG & NAIL IN NORTHERLY SIDE OF POWER POLE	AZ.	320°	67.36 FEET
A.C. REMON TAG & NAIL IN NORTHWEST SIDE OF 16" POPLAR	AZ.	170°	54.60 FEET
A.C. REMON TAG & NAIL IN SOUTHEAST SIDE OF 14" MAPLE	AZ.	255°	64.00 FEET
A.C. REMON TAG & NAIL IN WESTERLY SIDE OF 15" TW. OAK	AZ.	345°	81.17 FEET
CENTERLINE OF ASPHALT ROAD	AZ.	00°	5.0 FEET

Signed by George J. Mitchell Date November 15, 1996

Surveyor's Michigan License No. ....19618.....

GOVERNMENT CORNER HISTORY  
 NORTH QUARTER POST OF SECTION 5  
 TOWN 2 NORTH, RANGE 16 WEST

D-1

ORIG, GOV. SURVEY	NOT SET SOUTH QUARTER POST SEC 32, T3N, R16W SET 40.00 WEST OF SE COR.												
OLD NOTES 1891	FD PLOW PT. 40.00 CH WEST OF NE COR. SHOWS DISTANCE OF 728' WEST TO IRON ON LAKE MICHIGAN BLUFF												
OLD NOTES (NO DATE)	FROM SURVEY IN SECTION 32 SAUGATUCK FD IRON - 2626 FT EAST TO SE CORNER SHOWS DISTANCE OF 728' WEST TO IRON ON LAKE MICHIGAN BLUFF <u>WITNESSES FOR SAUGATUCK CORNER</u> <table border="0" style="margin-left: 20px;"> <tr><td>26" ASH</td><td>SE</td><td>24.5'</td></tr> <tr><td>26" ASH</td><td>SW</td><td>20.9'</td></tr> <tr><td>40" ELM</td><td>NE</td><td>51.8'</td></tr> <tr><td>12" ASH</td><td>NW</td><td>31.2'</td></tr> </table>	26" ASH	SE	24.5'	26" ASH	SW	20.9'	40" ELM	NE	51.8'	12" ASH	NW	31.2'
26" ASH	SE	24.5'											
26" ASH	SW	20.9'											
40" ELM	NE	51.8'											
12" ASH	NW	31.2'											
MDOT 1962	FD 1" IRON BAR <table border="0" style="margin-left: 20px;"> <tr><td>36" ELM</td><td>N61E</td><td>53.67'</td></tr> <tr><td>13" ASH</td><td>N22W</td><td>31.76'</td></tr> <tr><td>26" ASH</td><td>S23W</td><td>21.82'</td></tr> </table> EAST 2626.66' TO SE COR. SEC 32 SAUGATUCK EAST 2639.85' TO NE COR. SEC 5 GANGES MDOT RECORDS SHOW N1/4 POST, 5 & S1/4 POST, 32 AS A COMMON CORNER	36" ELM	N61E	53.67'	13" ASH	N22W	31.76'	26" ASH	S23W	21.82'			
36" ELM	N61E	53.67'											
13" ASH	N22W	31.76'											
26" ASH	S23W	21.82'											
RATEKIN WITNESS CARD	IRON IN MON BOX <table border="0" style="margin-left: 20px;"> <tr><td>C. CONC CULVERT</td><td>N15E</td><td>38.85'</td><td>CK 1996</td></tr> <tr><td>C. CONC CULVERT</td><td>S15E</td><td>28.45'</td><td>CK 1996</td></tr> <tr><td>C. PAVEMENT</td><td>NORTH</td><td>5.8'</td><td>CK 1996</td></tr> </table> 2627.09' EAST TO SAUGATUCK COR. CK 1996 JOG AT EAST GOVT 7.26' MEAS 13.2' CK 1996	C. CONC CULVERT	N15E	38.85'	CK 1996	C. CONC CULVERT	S15E	28.45'	CK 1996	C. PAVEMENT	NORTH	5.8'	CK 1996
C. CONC CULVERT	N15E	38.85'	CK 1996										
C. CONC CULVERT	S15E	28.45'	CK 1996										
C. PAVEMENT	NORTH	5.8'	CK 1996										
RATEKIN 9/18/72	L.C.R.C. L.2, P. 33 (SAME AS ABOVE)												
MITCHELL 11/1/78 & 5/19/92	IRON IN MON BOX <table border="0" style="margin-left: 20px;"> <tr><td>10" MAPLE</td><td>WSW</td><td>64.00</td><td>CK 1996</td></tr> <tr><td>P.P.</td><td>WNW</td><td>67.30</td><td>CK 1996</td></tr> </table> NAIL IN T/W. GUARD RAIL POST ESE 77.65' GONE CENTER M-89 NORTH 5' CK 1996	10" MAPLE	WSW	64.00	CK 1996	P.P.	WNW	67.30	CK 1996				
10" MAPLE	WSW	64.00	CK 1996										
P.P.	WNW	67.30	CK 1996										
T. & H. ASSOC. (NO DATE)	IRON IN MON BOX APPROX 0.2 MI. WEST OF WEST END OF BRIDGE ON M-89. THIS 1/4 CORNER IS COMMON TO SECTION NORTH.												
MITCHEL 1996	FD BOAT SPIKE IN MONUMENT BOX MEAS 2627.15' EAST TO SAUGATUCK CORNER MEAS 2640.40' EAST TO NE COR SEC 5 GANGES												